



Solid Waste & Recycling Transfer Station

Feasibility Study 18-11171-C



City Council Work Session

November 5, 2019



Presented by:



Kevin McCarthy & Ruth Abbe

PROJECT GOALS

- ❑ **State-of-the-art Solid Waste and Recycling Transfer Station:**
 - **Zero Waste Goals**
 - Maximizes recovery of reusable and recyclable materials to meet the City's zero waste goal
 - Ensures highest and best use of recovered materials
 - Facility that provides a maximum amount of space for the separation of materials for recovery
 - **User-friendly for customers, city staff, and city contractors**
 - **Sensitive to potential neighborhood and environmental impacts**

PROJECT GOALS Cont.

- ❑ **State-of-the-art Solid Waste and Recycling Transfer Station:**
 - Ensures environmental health & safety of the workers & visitors
 - **Climate Action Goals**
 - Supports GHG emissions reduction targets
 - Infrastructure for future electrification of collection fleet
 - Net Zero Energy Facility
 - Leadership in Energy and Environmental Design (LEED) Certified Facility


EXISTING SITE TODAY

- ❑ 37 years old (opened in 1982)
- ❑ 7.45-acres site including:
 - Transfer Station (TS)
 - Recycling Center
 - Vehicle Maintenance
- ❑ 137,885 tons of materials handled in 2017 from Berkeley and adjacent cities
- ❑ 75,448 tons of garbage in 2017 transferred to landfill annually
- ❑ 62,437 tons reused, recycled or composted annually



FACILITY OVERVIEW

Berkeley Transfer Station Tons (2017)



Materials	Collection Trucks	Self-Haul	Total¹
Reuse salvage @ Transfer Station	--	784	784
Recycling Center	12,620	3,367	15,987
Organics @ Transfer Station	21,177	12,303	33,480
Construction & demolition @ Transfer Station	--	12,186	12,186
Refuse @ Transfer Station	33,356	36,892	70,248
Total at Transfer Station	54,533	62,165	116,698
Total at Transfer Station + Recycling Center	67,153	65,532	132,685
Diversion %	50.3%	43.7%	47.1%

1 – Does not include MRF residual and cleanup of illegal dumping; approx. 5,200 TPY.

FACILITY OVERVIEW

Current Transfer Station vs Future Transfer Station

Current



Future




STAKEHOLDER & PUBLIC ENGAGEMENT

NOVEMBER-DECEMBER 2018

Listening Sessions (3 meetings)
Desired Transfer Station Features

JANUARY 2019

Design Charrette (3 days)
Develop Preliminary Concept
Plans for Facility



MARCH 2019

*Review Three Primary Concept
Plans (2 meetings)*




MAY 2019-WORKSHOP

*Revised Concept Plans based on Community & Stakeholder Feedback
(1 meeting)*



STAKEHOLDER & PUBLIC ENGAGEMENT

JANUARY 2019 - *Design Charrette (3 days)* Develop Preliminary Concept Plans for Facility



TWO CONCEPT PLANS (A & B) - SUMMARY

- ❑ Two facility design concepts were developed from extensive and valuable input from the community & stakeholder engagement process as well as programming input from City staff for current and future requirements
- ❑ Both design concept plans have much in common and both received support from community members and key stakeholders in the engagement/outreach process
- ❑ Main difference between two concept plans is Option A has a single material recovery facility (MRF)/Transfer Station building and Option B has separate buildings for the MRF and Transfer Station
- ❑ More than a dozen concept plan iterations were eliminated due to factors such as inefficient circulation, limited capacity, and/or significant cost impacts



TWO CONCEPT PLANS (A & B) – SUMMARY Cont.

- ❑ **Design Layout Characteristics in Common:**
 - Self-haul queuing capacity at the north end of Second Street based on repositioning of the cul-de-sac
 - Public buyback and drop-off center close to the corner of Gilman Street and Second Street to facilitate the heavy use from pedestrian walk-in customers
 - Separation of public and collection truck traffic through use of separate scale entrances.
 - Each concept plan also has similar public amenities and sustainability features



TWO CONCEPT PLANS (A & B) – SUMMARY Cont.


□ Both concept plans incorporate a diverse array of sustainability and community engagement features including:

- **Net Zero Energy and LEED Certification**
 - Photovoltaic panels on roof & canopy structures
 - Elevated wind turbines for on-site production of power
 - Rainwater capture and reuse features
 - Electric charging stations for staff vehicles
 - Design for future electrification of collection fleet




TWO CONCEPT PLANS (A & B) – SUMMARY Cont.

- **Community Outreach & Empowerment Features**
 - Environmental education center and public tour program
 - Creek walk (pathway) w/ educational kiosks and watershed art on Codornices Creek
 - Community and Artisan space for learning opportunities that explore common sense activities for creative reuse
 - Public kiosks for customers to attain zero waste and sustainability information
 - Community (civic) art onsite opportunities



SITE CONCEPT PLAN A

SINGLE BUILDING CONCEPT




Creek Restoration

Public Traffic at Second Street (North end)

Single MRF/TS Building

Truck Traffic along eastern site boundary


Community Buyback & Drop-off at Gilman Street



Concept A – Rendering Aerial View (from west, southwest)

SITE CONCEPT PLAN B

TWO BUILDING CONCEPT




Creek Restoration

Public Traffic at Second Street (North end)

Two Buildings, 1 MRF and 1 TS

Truck Traffic along eastern site boundary

Community Buyback & Drop-off at Gilman Street



Concept B – Rendering Aerial View (from west, southwest)

Development of Cost Analysis Framework

- ❑ ZWC Design Team developed plans, sections, and elevations with dimensions and keynote information for future use in developing preliminary cost estimates
- ❑ Future Project Cost Analysis should include following components:
 - *Site Improvements* (e.g., grading and paving, utilities relocation and undergrounding, etc.)
 - *Building Improvements* (e.g., TS, MRF, scale house, admin. offices, vehicle maintenance, etc.)
 - *Facility Equipment* (e.g., MRF sorting and processing equipment)
 - *Facility and Energy Sustainability* (e.g., infrastructure for electrification of collection fleet, photovoltaic panels, rainwater harvest tanks, wind turbines, etc.)
 - *Project Escalation Factor* from 2019 to projected bids for construction
 - *Contractors' indirect costs* (overhead and profit)

Development of Cost Analysis Framework Cont.

Cost Analysis Components cont.

- *Design contingency cost per the AACE International Design Practices*
- *Contractor planning permits and construction inspection/compliance*

Project Permitting Costs

Following project costs have been included in the ongoing Rate Study in development:

- *Solid Waste & Recycling Feasibility Study - \$500,000 (FY2019/2020)*
- *California Environmental Quality Act (CEQA) Study - \$5,000,000 (FY2020 – FY2025)*
- *Geotechnical site investigation - \$1,000,000 (completed during CEQA process through FY2021/2022)*
- *Final Design, and Plans & Specifications Engineering - \$3,000,000 (FY2026/2027)*

POTENTIAL FINANCIAL MODEL

FINANCIAL MODEL COMPONENTS

- ❑ A financial model should be developed to identify source of funds (revenues) and associated cash flow to ensure Zero Waste Enterprise can pay for project cost estimates.
- ❑ There are four potential sources of revenues for the City to pay for project costs as follows:
 - Tipping fees charged to self-haul (public) customers using the Berkeley Transfer Station
 - Collection rates charged to residential and commercial customers in the City of Berkeley
 - Zero Waste Fund Balance – operating and capital reserve
 - Debt financing through issuance of solid waste revenue bonds

Current Operations vs. Future – Buyback & Drop-Off Center

Current



Future



Current Operations vs. Future – Scale Entrance

Current



Future



NEXT STEPS

WHERE DO WE GO FROM HERE?

- Community Member and City Council Input & Feedback
- CEQA Process
- Financial Feasibility Analysis
- Final Facility Design and Permitting
- Facility Construction
- Commence New Operations



QUESTIONS / INPUT

