GROVE PARK FIELD AND PLAYGROUND RENOVATIONS

2828 Martin Luther King Jr. Way, Berkeley, CA 94703

COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218

PROJECT DIRECTORY

City of Berkeley Parks & Recreation and Waterfront Department 1947 Center St, 5th Floor Phone: (510) 981-6346 Berkeley, CA 94704

Wendy Wellbrock, Project Manager

LANDSCAPE ARCHITECT / CIVIL ENGINEER / STRUCTURAL ENGINEER RRM Design Group

325 Davis Street San Leandro, CA 94577

Phone: (510) 751-4910 Fax: (805) 543-4609

Julian Simeoni, Project Manager

GEOTECHNICAL

399 Lindbergh Avenue Livermore, CA 94551

Phone: (925) 315-3151 Fax: (925) 315-3152

Fax:

Natron Consulting Engineers

1480 Moraga Road, Suite C #229 Phone: (510) 847-9041

Moraga, CA 94556 Ron Zeiger, P.E.

PROJECT DESCRIPTION

- THE PROJECT GENERALLY INCLUDES BUT IS NOT LIMITED TO:
- RENOVATED SOFTBALL FIELD, INCLUDING FIELD TURF GRASS, IRRIGATION, DUGOUTS, FENCES, SPORTS NETTING, BACKSTOP, AND
- REPLACEMENT OF FIELD LIGHTING CONTROLS. RENOVATION OF AGES 2-5 AND 5-12 PLAYGROUNDS AND PICNIC
- NEW FURNISHINGS.
- NEW CONCRETE AND ASPHALT FLATWORK. DRAINAGE IMPROVEMENTS.

CODES

 ALL CONSTRUCTION SHALL CONFORM TO THE 2019 CALIFORNIA BUILDING, FIRE, MECHANICAL, PLUMBING, ELECTRICAL, ENERGY CODE, CALIFORNIA BUILDING CODE AND GREEN BUILDING CODE.

DIG ALERT DIAL TOLL FREE



BEFORE YOU DIG



BID ALTERNATE SUMMARY						
NO.	DESCRIPTION	REFERENCE				
1	BASE BID: INSTALL TURF SOD. (DEDUCT) REMOVE SOD SCOPE & REPLACE WITH TURF GRASS SEED INSTALLATION.	LC101/ LP101				
2	BASE BID: PROTECT EXISTING WOOD WALL, FENCE POSTS, FABRIC AND FOOTINGS ALONG NORTHEASTERN STRETCH OF FIELD. (ADD) DEMOLISH EXISTING WOOD WALL AND REPLACE WITH CONCRETE WALL. REPLACE CHAIN LINK FENCE POSTS, FOOTINGS, AND FABRIC.	DM101 / LC102				

SHEET INDEX

ADMINISTRATIVE USE PERMIT CONDITIONS OF APPROVAL GENERAL CONSTRUCTION NOTES AND ABBREVIATIONS

EXISTING CONDITIONS / TOPOGRAPHIC SURVEY

ACCESSIBILITY PLAN

DEMOLITION NOTES

DEMOLITION AND TREE PROTECTION PLAN DEMOLITION FENCE PHOTO SHEET

EROSION CONTROL NOTES AND DETAILS CE101 EROSION CONTROL PLAN

CBMP001 CITY BMP SHEET

CG101 GRADING AND DRAINAGE PLAN CG401 GRADING AND DRAINAGE BALLFIELD ENLARGEMENT PLAN

CG402 GRADING AND DRAINAGE PLAYGROUND ENLARGEMENT PLAN

CW101 STORMWATER MANAGEMENT PLAN

HORIZONTAL CONTROL PLAN

HORIZONTAL CONTROL POINT TABLE

CONSTRUCTION PLAN

CONSTRUCTION PLAN - FENCE & WALL LAYOUT

CONSTRUCTION PLAN - BACKSTOP & DUGOUT ENLARGEMENT CONSTRUCTION PLAN - PLAYGROUND AREA ENLARGEMENT

CONSTRUCTION DETAILS

CONSTRUCTION DETAILS LC502

LC503 CONSTRUCTION DETAILS CONSTRUCTION DETAILS

CONSTRUCTION DETAILS

CONSTRUCTION DETAILS

CONSTRUCTION DETAILS CONSTRUCTION DETAILS

GENERAL NOTES & STRUCTURAL DETAILS

LI001 **IRRIGATION NOTES**

LI101 IRRIGATION PLAN IRRIGATION DETAILS

PLANTING PLAN

ELECTRICAL LEGEND AND DETAILS

E-2.1 ELECTRICAL SITE PLAN E-2.2 ELECTRICAL SITE PLAN

PROJECT INFORMATION

TOTAL IRRIGATED LANDSCAPE AREA: 44,800 SF

TOTAL EXISTING HARDSCAPE AREA: 8,151 SF

TOTAL HARDSCAPE AREA TO BE REPLACED: 2,577 SF

TOTAL PROJECT AREA: 1.9 ACRES

DEFFERED SUBMITTALS

PLAY EQUIPMENT FOOTINGS - FOOTING ENGINEERING LC101/LC402 BALL NET POSTS AND ATTACHMENTS LC102/LC504

SET

BID

G00[°]



rrmdesign.com | (510) 751-4910 325 Davis St. San Leandro, CA 94577





Berk Ш S

NO. REVISION

COB SPECIFICATION NO. 22-11538-C

CITY PLAN NO. 8256 FILE NO. 406-218 **PROJECT MANAGER**

> JULIAN SIMEONI DRAWN BY CHECKED BY

PROJECT NUMBER 2211-01-RC21

NOVEMBER 22, 2022

The following conditions, as well as all other applicable provisions of the Zoning Ordinance, apply to this Permit:

1. Conditions Shall be Printed on Plans

The conditions of this Permit shall be printed on the second sheet of each plan set submitted for a building permit pursuant to this Use Permit, under the title 'Use Permit Conditions'. Additional sheets may also be used if the second sheet is not of sufficient size to list all of the conditions. The sheet(s) containing the conditions shall be of the same size as those sheets containing the construction drawings; 8-1/2" by 11" sheets are not acceptable.

2. Applicant Responsible for Compliance with Conditions

The applicant shall ensure compliance with all of the following conditions, including submittal to the project planner of required approval signatures at the times specified. Failure to comply with any condition may result in construction being stopped, issuance of a citation, and/or modification or revocation of the Use Permit.

3. Uses Approved Deemed to Exclude Other Uses (BMC Section 23B.56.010)

- A. This Permit authorizes only those uses and activities actually proposed in the application, and excludes other uses and activities.
- B. Except as expressly specified herein, this Permit terminates all other uses at the location subject to it.

4. Modification of Permits (BMC Section 23B.56.020)

No change in the use or structure for which this Permit is issued is permitted unless the Permit is modified by the Zoning Officer.

5. Plans and Representations Become Conditions (BMC Section 23B.56.030)

Except as specified herein, the site plan, floor plans, building elevations and/or any additional information or representations, whether oral or written, indicating the proposed structure or manner of operation submitted with an application or during the approval process are deemed conditions of approval.

6. Subject to All Applicable Laws and Regulations (BMC Section 23B.56.040)

The approved use and/or construction is subject to, and shall comply with, all applicable City Ordinances and laws and regulations of other governmental agencies. Prior to construction, the applicant shall identify and secure all applicable permits from the Building and Safety Division, Public Works Department and other affected City divisions and departments.

7. Exercised Permit for Use Survives Vacancy of Property (BMC Section 23B.56.080) Once a Permit for a use is exercised and the use is established, that use is legally recognized, even if the property becomes vacant, except as set forth in Standard Condition #8, below.

G:\LANDUSE\Projects by Address\Martin Luther King\2828\ZP2020-0071\DOCUMENT FINALS\2020-09-10_APFC__2828 MLK.docx

2828 Martin Luther King Jr. Way Page 4 of 8

NOTICE OF ADMINISTRATIVE DECISION - Findings and Conditions Administrative Use Permit #ZP2020-0071

8. Exercise and Lapse of Permits (BMC Section 23B.56.100)

- A. A permit for the use of a building or a property is exercised when, if required, a valid City business license has been issued, and the permitted use has commenced on the
- B. A permit for the construction of a building or structure is deemed exercised when a valid City building permit, if required, is issued, and construction has lawfully commenced.
- C. A permit may be declared lapsed and of no further force and effect if it is not exercised within one year of its issuance, except that permits for construction or alteration of structures or buildings may not be declared lapsed if the permittee has: (1) applied for a building permit; or, (2) made substantial good faith efforts to obtain a building permit and begin construction, even if a building permit has not been issued and/or construction has not begun.

9. Indemnification Agreement

The applicant shall hold harmless, defend, and indemnify the City of Berkeley and its officers, agents, and employees against any and all liability, damages, claims, demands, judgments or other losses (including without limitation, attorney's fees, expert witness and consultant fees and other litigation expenses), referendum or initiative relating to, resulting from or caused by, or alleged to have resulted from, or caused by, any action or approval associated with the project. The indemnity includes without limitation, any legal or administrative challenge, referendum or initiative filed or prosecuted to overturn, set aside, stay or otherwise rescind any or all approvals granted in connection with the Project, any environmental determination made for the project and granting any permit issued in accordance with the project. This indemnity includes, without limitation, payment of all direct and indirect costs associated with any action specified herein. Direct and indirect costs shall include, without limitation, any attorney's fees, expert witness and consultant fees, court costs, and other litigation fees. City shall have the right to select counsel to represent the City at Applicant's expense in the defense of any action specified in this condition of approval. City shall take reasonable steps to promptly notify the Applicant of any claim, demand, or legal actions that may create a claim for indemnification under these conditions of approval.

ADDITIONAL CONDITIONS IMPOSED BY THE ZONING OFFICER

Pursuant to BMC Section 23B.28.050.D, the Zoning Officer attaches the following additional conditions to this Permit:

Prior to Submittal of Any Building Permit:

10. Project Liaison. The applicant shall include in all building permit plans and post onsite the name and telephone number of an individual empowered to manage construction-related complaints generated from the project. The individual's name, telephone number, and responsibility for the project shall be posted at the project site for the duration of the project in a location easily visible to the public. The individual shall record all complaints received and actions taken in response, and submit written reports of such complaints and actions to the project planner on a weekly basis. Please designate the name of this individual

☐ Project Liaison WENDY WELLBROCK

G:\LANDUSE\Projects by Address\Martin Luther King\2828\ZP2020-0071\DOCUMENT FINALS\2020-09-10_APFC__2828 MLK.docx

Name

(510) 981-6346

Phone #

G:\LANDUSE\Projects by Address\Martin Luther King\2828\ZP2020-0071\DOCUMENT FINALS\2020-09-10_APFC__2828 MLK.docx

2828 Martin Luther King Jr. Way NOTICE OF ADMINISTRATIVE DECISION - Findings and Conditions Page 5 of 8 Administrative Use Permit #ZP2020-0071

Standard Construction-related Conditions Applicable to all Projects:

- 11. Transportation Construction Plan. The applicant and all persons associated with the project are hereby notified that a Transportation Construction Plan (TCP) is required for all phases of construction, particularly for the following activities:
- Alterations, closures, or blockages to sidewalks, pedestrian paths or vehicle travel lanes (including bicycle lanes);
- Storage of building materials, dumpsters, debris anywhere in the public ROW;
- Provision of exclusive contractor parking on-street; or
- Significant truck activity.

The applicant shall secure the City Traffic Engineer's approval of a TCP. Please contact the Office of Transportation at 981-7010, or 1947 Center Street, and ask to speak to a traffic engineer. In addition to other requirements of the Traffic Engineer, this plan shall include the locations of material and equipment storage, trailers, worker parking, a schedule of site operations that may block traffic, and provisions for traffic control. The TCP shall be consistent with any other requirements of the construction phase.

Contact the Permit Service Center (PSC) at 1947 Center Street or 981-7500 for details on obtaining Construction/No Parking Permits (and associated signs and accompanying dashboard permits). Please note that the Zoning Officer and/or Traffic Engineer may limit off-site parking of construction-related vehicles if necessary to protect the health, safety or convenience of the surrounding neighborhood. A current copy of this Plan shall be available at all times at the construction site for review by City Staff.

- 12. Construction activity shall be limited to between the hours of 8:00 a.m. and 6:00 p.m. on Monday through Friday, and between 9:00 a.m. and noon on Saturday. No constructionrelated activity shall occur on Sunday or on any Federal Holiday.
- 13. If underground utilities leading to adjacent properties are uncovered and/or broken, the contractor involved shall immediately notify the Public Works Department and the Building & Safety Division, and carry out any necessary corrective action to their satisfaction.
- 14. Subject to approval of the Public Works Department, the applicant shall repair any damage to public streets and/or sidewalks by construction vehicles traveling to or from the project
- 15. All piles of debris, soil, sand, or other loose materials shall be covered at night and during rainy weather with plastic at least one-eighth millimeter in thickness and secured to the ground.
- 16. All active construction areas shall be watered at least twice daily, and all piles of debris, soil, sand or other loose materials shall be watered or covered.
- 17. Trucks hauling debris, soil, sand, or other loose materials shall be covered or required to maintain at least two feet of board.
- 18. Public streets shall be swept (preferably with water sweepers) of all visible soil material carried from the site.

G:\LANDUSE\Projects by Address\Martin Luther King\2828\ZP2020-0071\DOCUMENT FINALS\2020-09-10_APFC__2828 MLK.docx

2828 Martin Luther King Jr. Way NOTICE OF ADMINISTRATIVE DECISION - Findings and Conditions Page 6 of 8 Administrative Use Permit #ZP2020-0071

- 19. The applicant shall establish and maintain drainage patterns that do not adversely affect adjacent properties and rights-of-way.
- 20. The applicant shall ensure that all excavation takes into account surface and subsurface waters and underground streams so as not to adversely affect adjacent properties and rights-of-way.
- 21. Any construction during the wet season shall require submittal of a soils report with appropriate measures to minimize erosion and landslides, and the developer shall be responsible for following these and any other measures required by the Building and Safety Division and the Public Works Department.
- 22. Halt Work/Unanticipated Discovery of Tribal Cultural Resources. In the event that cultural resources of Native American origin are identified during construction, all work within 50 feet of the discovery shall be redirected. The project applicant and project construction contractor shall notify the City Planning Department within 24 hours. The City will again contact any tribes who have requested consultation under AB 52, as well as contact a gualified archaeologist, to evaluate the resources and situation and provide recommendations. If it is determined that the resource is a tribal cultural resource and thus significant under CEQA, a mitigation plan shall be prepared and implemented in accordance with State guidelines and in consultation with Native American groups. If the resource cannot be avoided, additional measures to avoid or reduce impacts to the resource and to address tribal concerns may be required.
- 23. Archaeological Resources (Ongoing throughout demolition, grading, and/or construction). Pursuant to CEQA Guidelines Section 15064.5(f), "provisions for historical or unique archaeological resources accidentally discovered during construction" should be instituted.
- A. In the event that any prehistoric or historic subsurface cultural resources are discovered during ground disturbing activities, all work within 50 feet of the resources shall be halted and the project applicant and/or lead agency shall consult with a qualified archaeologist, historian or paleontologist to assess the significance of the
- B. If any find is determined to be significant, representatives of the project proponent and/or lead agency and the qualified professional would meet to determine the appropriate avoidance measures or other appropriate measure, with the ultimate determination to be made by the City of Berkeley. All significant cultural materials recovered shall be subject to scientific analysis, professional museum curation, and/or a report prepared by the qualified professional according to current professional standards.
- C. In considering any suggested measure proposed by the qualified professional, the project applicant shall determine whether avoidance is necessary or feasible in light of factors such as the uniqueness of the find, project design, costs, and other considerations.
- D. If avoidance is unnecessary or infeasible, other appropriate measures (e.g., data recovery) shall be instituted. Work may proceed on other parts of the project site while mitigation measures for cultural resources is carried out.
- E. If significant materials are recovered, the qualified professional shall prepare a report on the findings for submittal to the Northwest Information Center.

2828 Martin Luther King Jr. Way NOTICE OF ADMINISTRATIVE DECISION - Findings and Conditions Page 7 of 8 Administrative Use Permit #ZP2020-0071

- 24. Human Remains (Ongoing throughout demolition, grading, and/or construction). In the event that human skeletal remains are uncovered at the project site during grounddisturbing activities, all work shall immediately halt and the Alameda County Coroner shall be contacted to evaluate the remains, and following the procedures and protocols pursuant to CEQA Guidelines Section 15064.5 (e)(1). If the County Coroner determines that the remains are Native American, the City shall contact the California Native American Heritage Commission (NAHC), pursuant to Health and Safety Code Section 7050.5(c), and all excavation and site preparation activities shall cease within a 50-foot radius of the find until appropriate arrangements are made. If the agencies determine that avoidance is not feasible, then an alternative plan shall be prepared with specific steps and timeframe required to resume construction activities. Monitoring, data recovery, determination of significance and avoidance measures (if applicable) shall be completed expeditiously.
- 25. Paleontological Resources (Ongoing throughout demolition, grading, and/or construction). In the event of an unanticipated discovery of a paleontological resource during construction, excavations within 50 feet of the find shall be temporarily halted or diverted until the discovery is examined by a qualified paleontologist (per Society of Vertebrate Paleontology standards [SVP 1995,1996]). The qualified paleontologist shall document the discovery as needed, evaluate the potential resource, and assess the significance of the find. The paleontologist shall notify the appropriate agencies to determine procedures that would be followed before construction is allowed to resume at the location of the find. If the City determines that avoidance is not feasible, the paleontologist shall prepare an excavation plan for mitigating the effect of the project on the qualities that make the resource important, and such plan shall be implemented. The plan shall be submitted to the City for review and approval.

Prior to Issuance of Occupancy Permit or Final Inspection:

26. All construction at the subject property shall substantially conform to the approved Use Permit drawings or to modifications approved by the Zoning Officer.

27. All landscape, site and architectural improvements shall be completed per the attached approved drawings dated August 26, 2020.


At All Times (Operation):

- 28. All exterior lighting shall be energy efficient where feasible; and shielded and directed downward and away from property lines to prevent excessive glare beyond the subject
- 29. Noise and exterior lighting shall be controlled so as to prevent verified complaints from the surrounding neighborhood. This shall include noise created by employees working on the premises before or after patrons arrive.
- 30. <u>Drainage Patterns</u>. The applicant shall establish and maintain drainage patterns that do not adversely affect adjacent properties and rights-of-way. Drainage plans shall be submitted for approval of the Building & Safety Division and Public Works Department, if required.


G:\LANDUSE\Projects by Address\Martin Luther King\2828\ZP2020-0071\DOCUMENT FINALS\2020-09-10_APFC __2828 MLK.docx



rrmdesign.com | (510) 751-4910 325 Davis St. San Leandro, CA 94577



RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION



FIELD

GR

ш

, ШС Berk SP Way,

King 2828

NO. REVISION COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218 **PROJECT MANAGER** JULIAN SIMEONI DRAWN BY CHECKED BY

NOVEMBER 22, 2022 PROJECT NUMBER 2211-01-RC21

SHEET SET

BID

ABBREVIATIONS

AB	AGGREGATE BASE OR ANCHOR BOLT	LH	LEFT HAND
ABV AC	ABOVE ASPHALTIC CONCRETE	LOC LP	LOCATION LOW POINT
CP	ASPHALTIC CONCRETE PAVING	LS	LAG SCREW
DJ	ADJACENT	LT	LEFT
\GG	AGGREGATE	MAS	MASONRY
\LT	ALTERNATE	MATL	MATERIAL
PDD OY	ANGLE POINT	MAX	MAXIMUM
APPROX	APPROXIMATE	MED MFG	MEDIUM MANUFACTURING
ARCH EL	ARCHITECT (URAL) BELOW	MFR	MANUFACTURE(R)
LDG	BUILDING	MIN	MINIMUM
LK	BLOCK	MISC	MISCELLANEOUS
OT	BOTTOM	ML	MAINLINE
OW	BACK OF WALK	(N)	NEW
R	BOTTOM OF RAMP	NIC	NOT IN CONTRACT
RG	BEARING	NO	NUMBER
S CB	BOTTOM OF STEP CATCH BASIN	NOM NTS	NOMINAL NOT TO SCALE
F	CUBIC FOOT	OC	ON CENTER
)]	CAST IRON	OCEW	ON CENTER EACH WAY
CIP	CAST IN PLACE	OD	OUTSIDE DIAMETER
C/L	CENTERLINE	O.F.C.I.	OWNER FURNISHED, CONTRACTOR INSTALL
L	CENTERLINE	ОН	OVERHEAD
CLR	CLEAR	OPP	OPPOSITE OPTIONAL
MU	CONCRETE MASONRY UNIT	OPT PA	OPTIONAL PLANTER AREA
CO COL	CLEAN OUT COLUMN	PA PC	PLANTER AREA POINT OF CURVE
CONC	CONCRETE	PERF	PERFORATE (D)
CONST	CONSTRUCTION	PERP	PERPENDICULAR
CONT	CONTINUOUS, CONTINUE	PFE	PUBLIC FACILITIES EASEMENT
P	CENTER POINT	PL	PROPERTY LINE
R	CURB RETURN	POB	POINT OF BEGINNING
TC	CENTER TO CENTER	POC	POINT OF REVERSE CURVE
CTR	CENTER DIRECTION AS SHOWN	PRC	POINT OF REVERSE CURVE
AS ET	DIRECTION AS SHOWN DETAIL	PROP PSI	PROPOSED POUNDS PER SQUARE INCH
,,⊏1 DE	DRINKING FOUNTAIN	PT	POINT, POINT OF TANGENCY
) 	DRAIN INLET	PTDF	PRESSURE TREATED DOUGLAS FIR
IA	DIAMETER	PTL	PRESSURE TREATED LUMBER
IAG	DIAGONAL	PUE	PUBLIC UTLITIES EASEMENT
MI	DIMENSION	PVC	POLYVINYL CHLORIDE
S	DOWN SPOUT	R, RAD	RADIUS
)WG	DRAWING	RDWD	REDWOOD
A J	EACH EXPANSION JOINT	REBAR REF	REINFORCING BAR REFERENCE
LECT	ELECTRICAL	REM	REMOVE
LEV	ELEVATION	REQ'D	REQUIRED
NCL	ENCLOSURE	REV	revision(s), revised
Q	EQUAL	RIM	RIM ELEVATION OF STRUCTURE
QPT	EQUIPMENT	RH	RIGHT HAND
SMT	EASEMENT	ROW RT	RIGHT OF WAY RIGHT
WF X	ENGINEERED WOOD FIBER EXISTING	S S	SLOPE
XIST	EXISTING	SCH	SCHEDULE
Ξ)	EXISTING	SD	STORM DRAIN
AB	FABRICATION	SF	SQUARE FEET
30	FURNISHED BY OTHERS	SHT	SHEET
=	FINISHED FLOOR	SIM	SIMILAR
FE	FINISHED FLOOR ELEVATION	SL	SLOPE
G	FINISHED GRADE	SOG	SLAB ON GRADE
N L	FINISH (ED) FLOWLINE	SPEC SQ	SPECIFICATION(S) SQUARE
OC .	FACE OF CONCRETE	SS	SANITARY SEWER
OF .	FACE OF FINISH	\$/\$	STAINLESS STEEL
MC	FACE OF MASONRY	ST	STREET
OS	FACE OF STEP	STA	STATION
ND	FOUNDATION	STD	STANDARD
S T	FINISHED SURFACE	STL STRUC	STEEL STRUCTURE/ STRUCTURAL
ST TG	FINISHED SURFACE TURF FOOTING	SIRUC SUB	STRUCTURE/ STRUCTURAL SUBGRADE
JT	FUTURE	SURF	SURFACE
5A	GAGE, GAUGE	SWCL	SIDEWALK CENTERLINE
₿B	GRADE BREAK	SYS	SYSTEM
KT	GASKET	SYN	SYNTHETIC
SLV	GALLONS BER HOUR	TBC	TOP BACK OF CURB
SPH SPM	GALLONS PER HOUR GALLONS PER MINUTE	TC TF	TOP OF CURB TOP OF FOOTING
PM R	GRATE	TG	TOP OF FOOTING TOP OF GRATE
В	HOSE BIB	TP	TANGENT POINT
C	HANDICAPPED	TR	TOP OF RAMP
CAP	HANDICAPPED	TS	TOP OF STEP
DB	HEADBOARD	TW	TOP OF WALL
EX	HEXAGONAL	TYP	TYPICAL
OR	HORIZONTAL	UON	UNLESS OTHERWISE NOTED
IP IT	HIGH POINT	VAR	VARIES
T	HEIGHT	V.I.F. VERT	VERIFY IN FIELD VERTICAL
) TV	INSIDE DIAMETER INTERSECTION	VERI W	WATER
1 /	INVERT	W/	WITH
T	JOINT	W/O	WITHOUT
•	LENGTH	@	AT
В	LAG BOLT	ą.	CENTERLINE
		Ø	DIAMETER
		SF	SQUARE FEET

SUB GRADE ELEVATION

GENERAL CONSTRUCTION NOTES

- 1. PRIOR TO BEGINNING CONSTRUCTION, THE CONTRACTOR SHALL VERIFY ALL JOIN/EDGE CONDITIONS FOR GRADING, DRAINAGE, AND UNDERGROUND FACILITIES, INCLUDING LOCATION AND ELEVATION OF EXISTING FACILITIES AT CROSSINGS WITH PROPOSED UNDERGROUND FACILITIES. IF CONDITIONS DIFFER FROM THOSE SHOWN ON THE PLANS, THE CONTRACTOR SHALL NOTIFY THE CITY AND SHALL NOT BEGIN CONSTRUCTION UNTIL THE CHANGED CONDITIONS HAVE BEEN EVALUATED AND RESOLVED.
- 2. THE CONTRACTOR SHALL BECOME FAMILIAR WITH THE PLANS AND SITE CONDITIONS PRIOR TO BEGINNING WORK. SHOULD CONFLICTING INFORMATION BE FOUND ON THE PLANS, THE CONTRACTOR SHALL NOTIFY AND RECEIVE DIRECTION FROM THE CITY BEFORE PROCEEDING WITH THE WORK IN QUESTION.
- 3. ONLY "APPROVED" STAMPED AND SIGNED DRAWINGS SHALL BE USED FOR THE CONSTRUCTION OF THIS PROJECT.
- 4. NO CHANGES OR MODIFICATIONS TO THE PLANS SHALL BE MADE WITHOUT THE PRIOR WRITTEN APPROVAL OF THE CITY.
- 5. NO TREES, OTHER THAN THOSE INDICATED ON THE DRAWINGS, SHALL BE REMOVED WITHOUT PRIOR APPROVAL OF THE CITY.
- 6. ALL NUMERIC AND WRITTEN DIMENSIONS SHALL HAVE PRECEDENCE OVER ALL SCALE DIMENSIONS.
- 7. DETAILS AND NOTES ON THE DRAWINGS TAKE PRECEDENCE OVER TYPICAL DETAILS AND GENERAL NOTES.
- 8. WRITTEN SPECIFICATIONS TAKE PRECEDENCE OVER DRAWINGS.
- 9. ALL CONSTRUCTION SHALL CONFORM TO THE APPROVED PLANS AND SPECIFICATIONS.
- 10. CONTRACTOR SHALL TAKE ALL CARE TO PREVENT DISRUPTION OF PROJECT SITE IN AREAS OUTSIDE CONSTRUCTION ZONE.
- 11. THE CONTRACTOR SHALL NOTIFY THE CITY AT LEAST (72) HOURS BEFORE COMMENCING WORK.
- 12. PROPOSED DEVIATIONS FROM THE PLANS MUST BE SUBMITTED TO THE CITY FOR REVIEW AND APPROVAL, INCLUDING FIELD REVISIONS REQUESTED BY THE CITY INSPECTOR.
- 13. THE CONTRACTOR SHALL EMPLOY ALL LABOR, EQUIPMENT, AND METHODS REQUIRED TO PREVENT THEIR OPERATIONS FROM PRODUCING DUST IN AMOUNTS DAMAGING TO PROPERTY, CULTIVATED OR NATIVE VEGETATION, AND DOMESTIC AND NON-DOMESTIC ANIMALS OR CAUSING A NUISANCE TO PERSONS OCCUPYING BUILDINGS IN THE VICINITY OF THE JOB SITE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE CAUSED BY DUST RESULTING FROM THEIR OPERATIONS.
- 14. ALL STREETS, ALLEYS, VEHICULAR WAYS, SIDEWALKS, AND HAUL ROUTES SHALL BE KEPT CLEAN AND CLEAR OF DEBRIS, DIRT AND DUST IN A MANNER ACCEPTABLE TO THE CITY. AT A MINIMUM, THESE AREAS SHALL BE CLEANED AT THE END OF EACH WORK DAY. FAILURE TO DO SO WILL RESULT IN A "STOP WORK" NOTICE. SAID NOTICE WILL NOT BE RELEASED UNTIL THE AREA HAS BEEN CLEANED TO THE SATISFACTION OF THE CITY. THE FLUSHING OF DIRT OR DEBRIS INTO STORM DRAIN OR SANITARY SEWER FACILITIES IS NOT PERMITTED.
- 15. CONTRACTOR SHALL NOT INTERRUPT ANY SERVICES OR DISRUPT THE OPERATION OF ADJACENT BUSINESSES, RESIDENTIAL AREAS OR ONSITE FACILITIES OUTSIDE THE LIMIT OF WORK LINE.
- 16. CONSTRUCTION LINE AND GRADE STAKES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 17. CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OR PROPER RESETTING OF ALL EXISTING MONUMENTS AND OTHER SURVEY MARKERS. ANY SURVEY MONUMENTS DESTROYED BY THE CONTRACTOR SHALL BE REPLACED IN ACCORDANCE WITH THE STATE LAND SURVEYORS ACT AT THE CONTRACTOR'S EXPENSE.

- 18. ALL PROTECTIVE DEVICES TO BE INSTALLED BY THE CONTRACTOR AND SHALL BE IN PLACED AT THE END OF EACH WORK DAY. A SAFE PEDESTRIAN PATH OF TRAVEL SHALL BE PROVIDED AT ALL TIMES TO AND FROM BUILDING ENTRANCES TO PARKING FACILITIES. COORDINATE PEDESTRIAN WALK CLOSURES WITH CITY PRIOR TO CONSTRUCTION.
- 19. CONTRACTOR SHALL REFER TO MATERIALS SPECIFICATIONS THROUGHOUT THE APPROVED PLAN SET AND SPECIFICATIONS. ANY SUBSTITUTIONS OF THE MATERIALS SPECIFIED IN THESE DOCUMENTS SHALL REQUIRE WRITTEN APPROVAL FROM CITY.
- 20. DURING THE COURSE OF WORK, THE CONTRACTOR SHALL BE RESPONSIBLE FOR CALLING THE CITY FOR TESTING AND INSPECTION 24 HOURS IN ADVANCE. WORK NOT PROPERLY TESTED AND INSPECTED WILL BE SUBJECT TO REJECTION.
- 21. WORK IN AND ALONG PUBLIC STREETS AND PARKING LOTS, ONCE BEGUN, SHALL PROCEED TO COMPLETION WITHOUT DELAY SO AS TO PROVIDE MINIMUM INCONVENIENCE TO THE
- 22. CONTRACTOR SHALL BE RESPONSIBLE FOR THE VERIFICATION OF LOCATION AND DEPTH OF ALL EXISTING UTILITIES IN THE FIELD PRIOR TO CONSTRUCTION AND FOR PROTECTING SAME DURING CONSTRUCTION. BRING ANY CONFLICTS WITH NEW IMPROVEMENTS IMMEDIATELY TO THE ATTENTION OF THE CITY. ALL UTILITIES SHALL BE PROTECTED AND REPAIRED BY THE CONTRACTOR IF DAMAGED AT NO ADDITIONAL COST TO THE
- 23. NOTIFY UNDERGROUND SERVICE ALERT (USA) TOLL FREE AT 811 A MINIMUM OF (48) WORKING HOURS PRIOR TO THE START OF CONSTRUCTION.
- 24. CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR NOTIFICATION OF ALL UTILITY COMPANIES THAT ARE NOT A USA MEMBER A MINIMUM OF (48) HOURS PRIOR TO THE BEGINNING OF WORK.
- 25. ENTRANCE TO THE SITE AND LAY DOWN AREA DURING CONSTRUCTION SHALL BE SPECIFIED BY THE CITY OF BERKELEY.
- 26. CONTRACTOR SHALL PROVIDE DE-WATERING IF IT IS REQUIRED, AND SHALL COMPLY WITH ALL REQUIREMENTS OF THE REGIONAL WATER QUALITY CONTROL BOARD AND OTHER APPLICABLE AGENCIES.
- 27. UPON COMPLETION OF THE WORK, CONTRACTOR TO FURNISH TO THE CITY 'RECORD' DRAWINGS OF THE PROJECT, WHICH SHALL BE REVIEWED PRIOR TO THE ACCEPTANCE OF THE PROJECT. THE COMPLETE RECORD DRAWINGS SET SHALL BE CURRENT WITH ALL CHANGES AND DEVIATIONS REDLINED AS A PRECONDITION TO THE FINAL PROGRESS PAYMENT APPROVAL AND/OR FINAL CITY ACCEPTANCE.
- 28. ALL CONSTRUCTION SHALL CONFORM TO LATEST EDITION OF CALIFORNIA BUILDING CODE TITLE 24.
- 29. ALL CONSTRUCTION ACTIVITIES SHALL BE LIMITED TO MONDAY THROUGH FRIDAY OF THE CALENDAR WEEK. NO WEEKEND WORK SHALL BE PERMITTED WITHOUT THE PRIOR APPROVAL OF THE CITY'S AUTHORIZED REPRESENTATIVE.
- 30. THE CONTRACTOR IS TO ENSURE ALL APPLICABLE PERMITS ARE IN PLACE (INCLUDING ANY DEFERRED SUBMITTALS / PERMITS) BEFORE COMMENCING CONSTRUCTION.
- 31. THE CONTRACTOR IS TO ENSURE THAT ANY WORK IN THE PUBLIC RIGHT-OF-WAY THAT IS DAMAGED DURING CONSTRUCTION IS TO BE REPLACED PER THE CITY OF BERKELEY STANDARD DETAILS AND SPECIFICATIONS AT NO ADDITIONAL COST TO THE CITY.


TYPICAL SYMBOL LEGEND

SYMBOL	DESCRIPTION
X Y	DETAIL CALLOUT, WHERE 'X' = DETAIL NUMBER, AND 'Y' = PAGE NUMBER
$\frac{1}{X}$	SECTION CALLOUT, WHERE 'X' = SECTION NUMBER AND 'Y' = PAGE NUMBER
X	ELEVATION CALLOUT, WHERE 'X' = ELEVATION NUMBER AND 'Y' = PAGE NUMBER
XX-01	REFERENCE NOTE CALLOUT
	BREAKLINE
	CENTERLINE
	LIMIT OF WORK LINE


NOTE: DISCIPLINE-SPECIFIC SYMBOLS ARE SHOWN ON THEIR RESPECTIVE SHEETS.



rrmdesign.com | (510) 751-4910 325 Davis St. San Leandro, CA 94577



RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION



4 FIELD

Z AYGR

GR

NO.	REVISION		DATE
\triangle			
\triangle			
	DB SPECIFICATION Y PLAN NO. 825		
PROJ	IECT MANAGER		
	an simeoni		
	WN BY	CHECKED B	Y
DATE	<u> </u>	JS	
NO	VEMBER 22, 2	2022	
PROJ	IECT NUMBER		


KEY TO SHEET NUMBERING

DRAWING SHEET NUMBERING AND ORGANIZATION IS ADAPTED FROM THE UNITED STATES NATIONAL CAD STANDARD.

included.

DISC	CIPLINE DESIGNATORS - LEVEL 1 (Partial List)	DISC	CIPLINE DESIGNATORS - LEVEL 2 (Partial List)	SHE	ET TYPES
G R H V B C L S A	General Resource (Existing Conditions) Hazardous Materials Survey/Mapping Geotechnical Civil Landscape Structural Architectural	D S G E U C I P L	Demolition Site Grading Erosion Control Utilities Construction Irrigation Planting Lighting	0 1 2 3 4 5 6	General: Symbol legend, abbreviations, general notes. Plans Elevations Sections Large Scale Drawings: plans, elevations, sections (not details) Details Schedules and Diagrams
Е	Electrical	W	Stormwater	7	User Defined
Z	Contractor/Shop Drawings	Н	Horizontal Control	8 9	User Defined 3D Drawings: isometric, perspective, photos
		Das	h is substituted when Level 2 is not		


Sheet number at left (LC103) is LANDSCAPE CONSTRUCTION PLAN, THIRD SHEET.







RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION




Z W

NO. REVISION COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218

PROJECT MANAGER

DRAWN BY CHECKED BY

NOVEMBER 22, 2022 PROJECT NUMBER 2211-01-RC21



ACCESSIBILITY PLAN

<u>LEGEND</u>

■■■■ PROPOSED ACCESSIBLE ROUTE OF TRAVEL

4' MINIMUM WIDTH

• CROSS SLOPE ≤ 2%

 LONGITUDINAL SLOPE ≤ 5% MAX 1/4" LEVEL CHANGE AND 1/2" MAX

LEVEL CHANGE WITH EDGE TREATMENT TO ACCESSIBLE ROUTES.

EXISTING ACCESSIBLE ROUTE OF TRAVEL


NOTE: SEE CG SHEETS FOR MORE INFORMATION



rrmdesign.com | (510) 751-4910 325 Davis St. San Leandro, CA 94577



RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION



2828 Martin Luther King Jr. Way, Berkeley, K FIELD RENOV **ACCESSIBILITY** ARK

DATE NO. REVISION COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218

CHECKED BY

DRAWN BY

NOVEMBER 22, 2022 PROJECT NUMBER 2211-01-RC21

REFERENCE NOTES - PLAYGROUND

DESCRIPTION SYMBOL

D-01 REMOVE AND DISPOSE OF ALL RUBBER SURFACING AND ASSOCIATED BASE.

REMOVE AND DISPOSE OF EXISTING PARK SIGN, INCLUDING POSTS AND FOOTINGS. REPLACE WITH NEW SIGN (BY CITY).

REMOVE AND DISPOSE OF EXISTING DRINKING FOUNTAIN. D-04

REMOVE AND DISPOSE OF EXISTING PICNIC TABLES, GRILLS,

REMOVE AND DISPOSE OF ALL PLAY EQUIPMENT, INCLUDING

TO CITY CORP YARD. REMOVE AND DISPOSE OF CONCRETE

AND TRASH CANS. PATCH ANY DAMAGED CONCRETE.

FOOTINGS. REMOVE EXISTING BENCH SEAT AND POSTS AND TRANSPORT

REMOVE AND DISPOSE OF EXISTING VALVES AND VALVE BOXES.

REMOVE AND DISPOSE OF EXISTING ENGINEERED WOOD

EXISTING TO REMAIN SYMBOL **DESCRIPTION**

FOOTINGS.

EX-01 NOT USED

EX-08

EX-02 EXISTING ASPHALT/CONCRETE PAVING, PROTECT IN PLACE.

EX-03 EXISTING CONCRETE WALL, RETAIN AND PROTECT IN PLACE.

EXISTING SIGNAGE. REPLACE POLE AND RETAIN AND REUSE

RRM-2211.01-10

EX-04 EXISTING CONCRETE EDGE, PROTECT IN PLACE.

EX-05 RETAIN AND PROTECT EXISTING FABRICATED METAL FENCE AND CONCRETE EDGE.

EX-06 EXISTING IRRIGATION UTILITIES, RETAIN AND PROTECT IN PLACE.

EX-07 EXISTING LIGHT POLE, POST AND UTILITY BOX, PROTECT IN PLACE.

EXISTING ELECTRIC POLE, PROTECT IN PLACE. CAREFULLY REMOVE CONCRETE AROUND TO PROTECT FOOTING IN

EXISTING BOULDER, PROTECT IN PLACE.

PLACE.

CROWN DRIP LINE A. PRUNING TO BE PERFORMED BY CRITICAL ROOT ZONE CITY. NOTIFY URBAN FORESTRY TWO DAYS PRIOR. CONTRACTOR TO DISPOSE OF ALL DEBRIS. B. NO HEAVY EQUIPMENT SHALL OPERATE INSIDE THE PROTECTIVE FENCING INCLUDING DURING FENCE INSTALLATION AND REMOVAL. C. IF WORK IS BEING DONE WITHIN TREE PROTECTION FENCE: -THE DRIP LINE OUTSIDE OF THE HIGH DENSITY POLYETHYLENE PROTECTION FENCE OF TREES, WITH 3.5" x 1.5" OPENINGS; COVER AREA WITH 6" LAYER OF COLOR: ORANGE; COARSE TREE MULCH AND TOP STEEL POSTS INSTALLED (WITH PLYWOOD TO CREATE A AT 8' O.C. STABLE SURFACE FOR WALKING OR MOVING MACHINERY. 8.5" x 11" SIGN, LAMINATED IN PLASTIC SPACED EVERY - AREA OUTSIDE OF FENCING WITHIN 50' ALONG THE FENCE CRITICAL ROOT ZONE: NO HEAVY EQUIPMENT PERMITTED WITHIN THIS 2" X 6' STEEL POSTS — OR APPROVED EQUAL. KEEP OUT REE PROTECTION 5" THICK LAYER OF MULCH -WIDTH PFR PI AN USE HAND EQUIPMENT FOR PAVING REMOVAL WITHIN FENCING TREE PROTECTION

REFERENCE NOTES - FIELD

SYMBOL **DESCRIPTION**

D-104

D-101 REMOVE AND DISPOSE OF EXISTING ASPHALT AND CONCRETE PAVING.

D-102 EXISTING ASH TREE. GRIND STUMPS AND REMOVE STUMPS AS

REMOVE AND DISPOSE OF EXISTING WOOD SHEDS.

REMOVE AND SALVAGE EXISTING METAL SHEDS FOR RELOCATION. SEE LC101 FOR LOCATION.

D-105 EXISTING PEAR TREE. GRIND STUMPS AND REMOVE STUMPS AS

REMOVE AND DISPOSE OF ALL EXISTING BACKSTOP INCLUDING POSTS, FOOTINGS, RAILS, AND FABRIC. D-107

REMOVE AND DISPOSE OF EXISTING DUGOUTS INCLUDING POSTS, FENCE/INC FENCE FOOTINGS, CONCRETE STEPS, PAVING AND BENCHES. NEATLY SAWCUT EXISTING PAVEMENT WHERE EXISTING PAVEMENT IS TO BE RETAINED.

REMOVE AND DISPOSE OF LOW METAL POST AND FOOTING.

D-109 REMOVE APPROX. 15 LF (10 LF NORTH AND 5 LF SOUTH) CURB AND GUTTER AND 3 LF OF DAMAGED CURB DRAIN. PROTECT EXISTING CATCH BASIN IN PLACE. SEE CG402 FOR EXTENT OF REPAIR.

EXISTING DAWN REDWOOD TREE. GRIND STUMPS AND REMOVE AS SPECIFIED.

EXISTING TO REMAIN

SYMBOL DESCRIPTION **EX-101** EXISTING BIORETENTION SWALES AND ASSOCIATED UTILITIES,

 $\langle EX-102 \rangle$

NOT USED

RETAIN AND PROTECT IN PLACE.

EX-103 EXISTING ASPHALT/CONCRETE PAVING, PROTECT IN PLACE.

EX-104 NOT USED

(EX-112)

EX-105 EXISTING PITCHING RUBBER AND HOME PLATE, RETAIN AND PROTECT IN PLACE.

EX-106 EXISTING INFIELD MIX MATERIAL TO BE RETAINED/STOCKPILED AND REUSED.

EX-107 REMOVE AND SALVAGE EXISTING BOULDER TO BE RELOCATED. VERIFY LOCATION IN FIELD WITH LANDSCAPE ARCHITECT.

EXISTING LANDSCAPE BETWEEN FENCING AND SIDEWALK TO BE RETAINED AND PROTECTED.

EXISTING SPORTSFIELD LIGHT POLE, POST, AND UTILITY BOX, PROTECT IN PLACE.

EXISTING DRAIN, CONCRETE SURROUNDS AND GUTTER,

EXISTING BACKFLOW PREVENTOR AND RELATED IRRIGATION APPURTENANCES, PROTECT IN PLACE.

⟨EX-111 RETAIN AND PROTECT EXISTING FOUL POLE.

PROTECT IN PLACE. **EX-113** EXISTING DRAIN INLET, PROTECT IN PLACE.


EX-114 EXISTING NET POSTS, RETAIN AND PROTECT IN PLACE.

DEMOLITION NOTES


- 1. THIS DEMOLITION PLAN WAS PREPARED FOR THE CONVENIENCE OF THE CONTRACTOR. THE LANDSCAPE ARCHITECT AND THE ENGINEER DO NOT REPRESENT THAT ALL ITEMS WHICH MAY REQUIRE DEMOLITION AND REMOVAL HAVE BEEN SHOWN. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO CAREFULLY EXAMINE THE SITE AND DETERMINE AND EXECUTE ALL DEMOLITIONS AND REMOVALS NECESSARY FOR THE CONSTRUCTION OF THE NEW WORK TO THE SPECIFIED LINES, GRADES, AND CONFIGURATIONS.
- 2. DEMOLITION WORK AND ABANDONMENT SHALL CONFORM TO THE UNIFORM BUILDING CODE, TITLE 24.
- 3. NO DEMOLITION SHALL BE STARTED WITHOUT APPROVED PLANS. THE CITY SHALL BE NOTIFIED AT LEAST (48) HOURS PRIOR TO STARTING DEMOLITION.
- 4. THE PLANS DO NOT AUTHORIZE SITE DISTURBANCE BEYOND THE LIMIT OF WORK LINE AS REPRESENTED ON THE PLANS OR UNLESS OTHERWISE NOTED
- 5. ALL ITEMS DAMAGED DURING DEMOLITION AND CONSTRUCTION SHALL BE REPAIRED OR REPLACED TO ORIGINAL CONDITION OR BETTER TO THE SATISFACTION OF THE OWNER BY THE CONTRACTOR AT THE CONTRACTORS EXPENSE.
- 6. ALL ITEMS SCHEDULED FOR REMOVAL SHALL BE PROPERLY DISPOSED OF OFF-SITE. CONTRACTOR TO VERIFY WITH THE CITY PRIOR TO CONSTRUCTION.
- 7. THE CONTRACTOR SHALL SALVAGE AND DELIVER TO THE CITY CORP YARD ANY ITEMS AT THE REQUEST OF THE OWNER AS NOTED AS 'TO BE SALVAGED' ON
- 8. ALL DEBRIS FROM THE DEMOLITION PROCESS SHALL BE REMOVED FROM THE SITE AND DISPOSED OF AT THE CONTRACTOR'S EXPENSE UNLESS OTHERWISE NOTED.
- 9. ALL ABANDONED UTILITIES SHALL BE MARKED IN THE FIELD AND LOCATED ON THE DRAWINGS OF RECORD TO BE PREPARED BY THE CONTRACTOR.
- 10. THE CONTRACTOR SHALL ONLY REMOVE THOSE UNDERGROUND FACILITIES SPECIFICALLY NOTED FOR REMOVAL. DAMAGE TO EXISTING FACILITIES TO REMAIN SHALL BE CORRECTED AT THE CONTRACTOR'S EXPENSE.
- 11. CONTRACTOR SHALL COMPLY WITH ALL OF CITY CONSTRUCTION AND DEMOLITION RECYCLING DEBRIS REQUIREMENTS.
- 12. REMOVE SPECIFIED TREES AND GRIND TREE STUMPS INDICATED ON THE PLANS. REMOVE TREES, TOGETHER WITH THE BULK OF THE ROOTS, TO A MINIMUM DEPTH OF 24 INCHES BELOW EXISTING GRADE AND WITHIN A RADIUS OF 7 FEET BEYOND THE PERIMETER OF THE TRUNK AT GROUND LINE. CHIP AND STOCKPILE ON SITE FOR USE AS MULCH PER PLANTING PLANS. CITY ARBORIST TO REVIEW.
- 13. FILL AND COMPACT HOLES RESULTING FROM TREES AND TREE STUMP REMOVAL TO REQUIRED DENSITY. FILLING SHALL NOT BE DONE UNTIL HOLES HAVE BEEN APPROVED BY THE CITY'S REPRESENTATIVE. CITY ARBORIST TO REVIEW.
- 14. CLEAR AND GRUB ALL UNDERSTORY VEGETATION UNLESS NOTED OTHERWISE. CITY ARBORIST TO REVIEW.
- 15. CLEAR AND GRUB REMOVAL WITHIN DRIPLINES OF EXISTING TREES SHALL NOT EXCEED 3" IN DEPTH AND SHALL BE DONE BY HAND. CITY ARBORIST TO REVIEW.
- 16. PAVING REMOVAL WITHIN DRIPLINES OF EXISTING TREES SHALL BE DONE BY HAND ONLY.
- 17. EXISTING IRRIGATION AND WATER LINE LOCATIONS AND DEPTHS TO BE CONFIRMED IN THE FIELD BY THE CONTRACTOR. IF LOCATIONS CONFLICT WITH FOOTINGS, EARTHWORK, OR GRADING; WATER AND IRRIGATION LINES TO BE REMOVED PER CITY DIRECTION.
- 18. CONSTRUCTION FENCE SHALL BE INSTALLED AND REMAIN THROUGHOUT DURATION OF PROJECT CONSTRUCTION.
- 19. CONTRACTOR SHALL SAWCUT IN A CLEAN, STRAIGHT, LINE.
- 20. ANY UTILITIES NOT SHOWN FOR REMOVAL SHALL REMAIN OPERATIONAL DURING CONSTRUCTION. ANY SHUT OFF OF WATER UTILITIES SHALL BE LIMITED TO (48) HOURS MAXIMUM.
- 21. PRESERVE ALL EXISTING SIGNS UNLESS OTHERWISE NOTED.



rrmdesign.com | (510) 751-4910 325 Davis St. San Leandro, CA 94577



RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION



eley, Ш 4 200 Berk ш $\mathbb{F}_{\mathbf{X}}$

4

DATE NO. REVISION


COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218

PROJECT MANAGER

CHECKED BY DRAWN BY

NOVEMBER 22, 2022 PROJECT NUMBER 2211-01-RC21

SET BID




DEMOLITION LEGEND

SYMBOL	<u>TYPE</u>	DESCRIPTION
	CONCRETE TO BE REMOVED	REMOVE EXISTING CONCRETE PAVEMENT, ASSOCIATED AGGREGATE BASE (ASSUME 8" DEPTH) STAIRS, AND FOOTINGS.
	ASPHALT TO BE REMOVED	REMOVE EXISTING ASPHALT PAVEMENT, ASSUME 2" DEPTH
	CONCRETE TO BE RETAINED	PROTECT IN PLACE
	ASPHALT TO BE RETAINED	PROTECT IN PLACE
	CLEAR AND GRUB	EXISTING TURF, GROUNDCOVER, AND SHRUBS TO BE CLEARED, GRUBBED, AND REMOVED. ADJUST AND PROTECT ALL IRRIGATION PIPING, FITTINGS, HEADS, AND ASSOCIATED ITEMS TO ALLOW FOR NEW CONSTRUCTION.
	RUBBER SURFACING	REMOVE EXISTING RUBBER PLAY SURFACING AND ASSOCIATED BASE
	ENGINEERED WOOD FIBER	REMOVE AND DISPOSE EXISTING EWF. REPLACE WITH NEW EWF.
	EXISTING DECOMPOSED GRANITE	CLEAR WEEDS OR VEGETATION, REFRESH SURFACE OR ADD SECTION OF NEW LAYER AS NECESSARY, AND LEVEL SURFACE. REFER TO GRADING PLANS.
	EXISTING INFIELD FINES	RETAIN AND STOCKPILE FOR REUSE
	TREE TO REMAIN	PROTECT IN PLACE
X	TREE TO REMOVE	TREE TO REMOVE
xxxx	TREE PROTECTION FENCING	SEE DETAIL 1 DM001
xx	EXISTING FENCING	EXISTING CHAIN LINK FENCING, REFER TO NOTES ON PLAN EXISTING PREFABRICATED METAL FENCING
	SAWCUT	
	I	I

NOTE


1. SEE 6/LC502 FOR WOOD WALL DEMOLITION DETAIL. REFER TO DM201 FOR EXTENT OF DEMOLITION.



DM101

rrmdesign.com | (510) 751-4910 325 Davis St. San Leandro, CA 94577


RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION



NO.	REVISION		DATE
	OB SPECIFICATION Y PLAN NO. 825		
PROJ	IECT MANAGER		
JS			
DRAV	WN BY	CHECKED B	Y
YI		JS	
DATE			
NO	VEMBER 22, 2	2022	
PROJ	IECT NUMBER		
	2211-0	1-RC21	
SHEE	Т		








FIELD FENCE - BACKSTOP




FIELD FENCE - RUSSELL ST.




FIELD FENCE - GRANT ST.



rrmdesign.com | (510) 751-4910 325 Davis St. San Leandro, CA 94577



RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION



RK FIED REN

FENCI

NO. REVISION COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218

PROJECT MANAGER

DRAWN BY CHECKED BY

NOVEMBER 22, 2022 PROJECT NUMBER 2211-01-RC21

GENERAL EROSION CONTROL NOTES

- 1. THE CONTRACTOR SHALL BE OR DESIGNATE A QUALIFIED QSP. THE QSP (QUALIFIED SWPPP PRACTITIONER) SHALL HAVE THE APPROPRIATE TRAINING AND OVERSEE ALL IMPLEMENTATION OF THE SWPPP AND IT'S REQUIREMENTS. THE QSP SHALL BE RESPONSIBLE FOR ALL INSPECTIONS AND OBSERVATIONS OF THE BMP'S.
- 2. THE QSD (QUALIFIED SWPPP DEVELOPER) SHALL APPROVE AND CERTIFY ALL AMENDMENTS TO THE ANNUAL CERTIFICATIONS.
- 3. EROSION CONTROL SHEETS (PREPARED BY QSD) SHOWS THE WATER MONITORING LOCATION THAT HAS BEEN CHOSEN FOR THIS SITE BY THE QSD. THE QSP SHALL REVIEW THIS LOCATION AND REPORT BACK TO THE QSD IF THIS LOCATION IS DEEMED UNSAFE OR UNSUITABLE FOR ANY REASONS.
- 4. THE QSP SHALL ASSURE ALL SAFETY PRECAUTIONS NECESSARY HAVE BEEN
- IMPLEMENTED TO DO THE WATER MONITORING.
- 5. A STANDBY CREW FOR EMERGENCY WORK SHALL BE AVAILABLE AT ALL TIMES DURING THE RAINY SEASON (OCTOBER 15 THROUGH APRIL 15). NECESSARY MATERIALS SHALL BE AVAILABLE AND STOCKPILED AT CONVENIENT LOCATIONS TO FACILITATE RAPID CONSTRUCTION OF TEMPORARY DEVICES WHEN RAIN IS IMMINENT.
- 6. THE CONTRACTOR SHALL CONSTRUCT TEMPORARY EROSION CONTROL MEASURES AS SHOWN ON THIS PLAN AND/OR AS DIRECTED BY THE ENGINEER OR QSD TO CONTROL DRAINAGE WHICH HAS BEEN AFFECTED BY GRADING AND OR TRENCHING. 7. THE CONTRACTOR WILL BE ON CALL IN THE EVENT IT IS NECESSARY TO IMPLEMENT
- EROSION CONTROL MEASURES OR IN THE EVENT OF AN EMERGENCY. 8. ALL STORMWATER CONTROL MEASURES THAT ARE IDENTIFIED IN THE REAP (RAIN
- EVENT ACTION PLAN) SHALL BE IN PLACE MIN. OF 24 HRS. PRIOR TO FORECAST 9. AFTER A RAINSTORM, ALL BMP'S SHALL BE INSPECTED AND ANY BUILDUP OF
- SEDIMENTS SHALL BE REMOVED AND DISPOSED OF IN AN APPROVED MANNER. 10. THE ENGINEER OF RECORD, QSD OR AN AUTHORIZED REPRESENTATIVE MAY REQUIRE THE CONTRACTOR AT ANY TIME TO INSTALL AND OR CONSTRUCT ADDITIONAL DRAINAGE STRUCTURES AS NECESSARY TO PRÉVENT OR CONTROL
- 11. THE EROSION CONTROL DEVICES ON THIS PLAN ARE A GENERAL CONCEPT OF WHAT MAY BE REQUIRED. EROSION CONTROL DEVICES MAY BE RELOCATED, DELETED OR ADDITIONAL ITEMS MAY BE REQUIRED DEPENDING ON THE ACTUAL SOIL CONDITIONS ENCOUNTERED. EROSION CONTROL DEVICES MAY BE PLACED AT THE DISCRETION OF THE QSP AS APPROVED BY THE QSD.
- 12. THE CONTRACTOR IS RESPONSIBLE TO KEEP IN FORCE ALL EROSION CONTROL DEVICES AND TO MODIFY THOSE DEVICES AS SITE PROGRESS DICTATES.
- 13. THE CONTRACTOR SHALL MONITOR THE EROSION CONTROL DEVICES DURING STORMS AND MODIFY THEM IN ORDER TO PREVENT PROGRESS OF ANY ONGOING EROSION.
- 14. THE CONTRACTOR IS RESPONSIBLE FOR CLEANING ANY EROSION OR DEBRIS SPILLING ONTO A PUBLIC STREET DAILY.
- 15. THE CONTRACTOR SHALL CONTACT THE QSD IN THE EVENT THAT THE EROSION CONTROL PLAN AS DESIGNED REQUIRES ANY SUBSTANTIAL REVISIONS.
- 16. DURING GRADING OPERATIONS IF AN AREA OF DISTURBANCE IS TO REMAIN IDLE FOR A PERIOD OF 2 OR MORE WEEKS, THE DISTURBED AREAS SHALL BE COVERED WITH MULCH, STRAW OR SOME OTHER TYPE OF BMP TO PREVENT EROSION DURING RAIN EVENTS.
- 17. THE CONTRACTOR SHALL PROVIDE STREET SWEEPING AS DIRECTED BY INSPECTOR OR AS NEEDED THROUGHOUT THE DAY AND AT THE END OF EACH SHIFT TO PREVENT ANY SEDIMENTS FROM BEING TRACKED OFF-SITE OR TO AREAS THAT MAY CONTRIBUTE TO SEDIMENTS BEING DEPOSITED INTO THE STORM DRAIN SYSTEM. 18. POST CONSTRUCTION BMP'S INCLUDING PLANTINGS, SHRUBS, GROUND COVER AND
- TREES AS SHOWN ON THE CONSTRUCTION PLANS SHALL BE IN PLACE AS SOON AS
- 19. CONTRACTOR TO INSTALL SILT FENCING AT ALL PERIMETER LOCATIONS THAT HAVE THE POTENTIAL TO DISCHARGE STORMWATER OFF-SITE. 20. CONTRACTOR TO PROTECT ALL YARD AND LANDSCAPE AREA DRAINS FROM
- SEDIMENTS UNTIL LANDSCAPING IS COMPLETED AND VEGETATION ESTABLISHED. 21. GRAVEL BAGS ORIENTED TO SLOW THE FLOW OF STORM WATER RUNOFF SHALL BE
- PLACED IN THE CONCRETE GUTTERS IN THE ON-SITE ROADWAY TO HELP FILTER OUT ANY SEDIMENTS. THESE GRAVEL BAGS SHALL BE PLACED 50' O/C MAX. SEDIMENTS THAT ACCUMULATE AT THE GRAVEL BAGS SHALL BE REMOVED AFTER EACH RAIN EVENT. 22. THE CONTRACTOR SHALL KEEP TWO ACCEPTABLE RAIN GAUGES ON-SITE TO
- MONITOR RAIN EVENTS DURING CONSTRUCTION.
- 23. THE CONTRACTOR SHALL IMPLEMENT EFFECTIVE WIND EROSION CONTROLS
- 24. IN THE EVENT OF A RELEASE OF A REPORTABLE QUANTITY OF A POLLUTANT, THE CONTRACTOR SHALL ADVISE THE OWNER TO NOTIFY THE NATIONAL RESPONSE CENTER AND THE CITY OF BERKELEY. IF NECESSARY, THIS POLLUTION PREVENTION PLAN SHOULD BE REVISED TO REFLECT THE CHANGE IN CONDITIONS OF THE CONSTRUCTION ACTIVITY. A REPORTABLE QUANTITY IS ESTABLISHED BY THE 40 CODE OF FEDERAL REGULATIONS (CRI) 1117.3 OR 40 CFR 302.4.
- 25. EROSION CONTROL MEASURES SHALL BE IMPLEMENTED AND MAINTAINED TO THE SATISFACTION OF THE BUILDING OFFICIAL AND PUBLIC WORKS DIRECTOR DURING ALL DEMOLITIONS, CONSTRUCTION AND GROUND DISTURBING ACTIVITIES.
- 26. TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED WHEN PERMANENT IMPROVEMENTS, PLANTINGS, AND FACILITIES ARE IN PLACE. TEMPORARY MEASURES SHALL BE REMOVED PRIOR TO FINAL INSPECTION APPROVALS.
- 27. STOCKPILE MANAGEMENT SHALL BE IN CONFORMANCE WITH GENERAL PERMIT AND THE CASOA BMP GUIDE.
- 28. SEE CONSTRUCTION PLANS FOR MORE INFORMATION ON POST CONSTRUCTION VEGETATION BMP'S.
- 29. IF DURING CONSTRUCTION DEWATERING OPERATIONS BECOME NECESSARY, ALL DEWATERING SHALL BE DONE IN COMPLIANCE WITH THE REQUIREMENTS OUTLINED THE NPDES GENERAL PERMIT AND PER THE CASQA BMP HANDBOOK FOR BMP SC-11. DISCHARGES SHALL BE TREATED FOR EXCESSIVE SEDIMENTS PRIOR TO LEAVING THE SITE AND/OR ENTERING THE CITY OF BERKELEY'S STORM DRAIN SYSTEM.

AIR QUALITY CONTROL NOTES

THE FOLLOWING PRACTICES ARE TO BE USED AT ALL TIMES DURING CONSTRUCTION:

- REDUCE THE AMOUNT OF DISTURBED AREA WHERE POSSIBLE. 2. USE WATER TRUCKS OR SPRINKLER SYSTEMS IN SUFFICIENT QUANTITY TO PREVENT AIRBORNE DUST FROM LEAVING THE SITE. INCREASED WATERING FREQUENCY WILL BE REQUIRED WHENEVER WIND SPEEDS EXCEED 15MPH. RECLAIMED (NON-POTABLE
- WATER) WATER SHOULD BE USED WHENEVER POSSIBLE. 3. PERMANENT DUST CONTROL MEASURES IDENTIFIED IN THE APPROVED PROJECT PLANS SHALL BE IMPLEMENTED AS SOON AS POSSIBLE FOLLOWING COMPLETION OF ANY SOIL DISTURBING ACTIVITIES.
- 4. EXPOSED GROUND AREAS THAT ARE PLANNED TO BE REWORKED AT DATES GREATER THAN ONE MONTH AFTER INITIAL GRADING SHALL BE SOWN WITH A FAST GERMINATING NATIVE GRASS SEED AND WATERED UNTIL VEGETATION IS
- 5. ALL DISTURBED SOIL AREAS NOT SUBJECT TO RE-VEGETATION MUST BE STABILIZED USING APPROVED CHEMICAL SOIL BINDERS, JUTE NETTING, OR OTHER METHODS APPROVED IN ADVANCE BY THE CITY.
- 6. ALL ROADWAYS, DRIVEWAYS, SIDEWALKS, ETC. TO BE PAVED SHOULD BE COMPLETED AS SOON AS POSSIBLE. IN ADDITION, BUILDING PADS SHOULD BE LAID AS SOON AS POSSIBLE AFTER GRADING UNLESS SEEDING OR SOIL BINDERS ARE
- 7. VEHICLE SPEED FOR ALL CONSTRUCTION VEHICLES SHALL NOT EXCEED 15MPH ON ANY UNPAVED SURFACE AT THE CONSTRUCTION SITE.
- 8. ALL TRUCKS HAULING DIRT, SAND, SOIL, OR OTHER LOOSE MATERIAL ARE TO BE COVERED OR SHOULD MAINTAIN AT LEAST TWO FEET OF FREEBOARD (MINIMUM VERTICAL DISTANCE BETWEEN TOP OF LOAD AND TOP OF TRAILER) IN ACCORDANCE WITH THE CALIFORNIA VEHICLE CODE SECTION 23114.
- 9. INSTALL WHEEL WASHERS WHERE VEHICLES ENTER AND EXIT UNPAVED ROAD AND STREETS, OR WASH OFF TRUCKS AND EQUIPMENT LEAVING THE SITE.
- 10. SWEEP STREETS AT THE END OF EACH DAY IF VISIBLE SOIL MATERIAL IS CARRIED ONTO ADJACENT PAVED ROADS. WATER SWEEPERS WITH RECLAIMED WATER SHOULD BE USED WHERE FEASIBLE.
- 11. A DESIGNATED DUST CONTROL MONITOR SHALL BE CHOSEN. THEY SHALL BE RESPONSIBLE FOR IMPLEMENTATION OF ALL DUST CONTROL MEASURES. THE MONITOR SHALL BE AVAILABLE DURING WEEKENDS AND HOLIDAYS. THE NAME AND PHONE NUMBER OF THE MONITOR SHALL BE PROVIDED TO THE CITY AND APCD.

PHASING NOTES


- 1. THE CONTRACTOR SHALL PHASE CONSTRUCTION ROUGH GRADING TO LIMIT THE SIZE OF DISTURBANCE TO AN AREA THAT CAN BE MAINTAINED WITH PROPER BMP'S DURING ANY RAIN EVENTS.
- 2. AFTER AN AREA HAS BEEN PAVED, THE CONTRACTOR SHALL PROVIDE GRAVEL BAGS IN THE FLOW LINES TO FILTER SEDIMENTS FROM STORM WATER RUNOFF OR AN APPROVED EQUAL
- 3. AREA DRAINS SHALL HAVE STORM DRAIN INLET PROTECTION INSTALLED DURING THE TIME BETWEEN INSTALLATION AND PLANTING OF GROUND VEGETATION PER THE PLANS OR AN APPROVED EQUAL.
- 4. LANDSCAPED AREAS SHALL BE COMPLETED AND SPRINKLERS INSTALLED AS SOON AS POSSIBLE AFTER GRADING OPERATIONS.
- 5. ANY AREAS OF DISTURBANCE THAT WILL REMAIN IDLE FOR TWO OR MORE WEEKS SHALL BE STABILIZED WITH MULCH, STRAW, HYDROSEED OR OTHER APPROPRIATE
- 6. DURING ASPHALT PATCHING OPERATIONS, THE CONTRACTOR SHALL PROVIDE EITHER PERMANENT OR TEMPORARY PAVING IN THE AREAS OF PATCHING BY THE END OF THE WORK DAY. NO TRENCHES SHALL BE LEFT OPEN DURING TIMES OF PREDICTED RAINFALL.
- 7. THE AREAS SHOWN ON THE PLANS FOR MATERIAL DELIVERY & STORAGE AND CONCRETE WASTE MANAGEMENT ARE FOR REFERENCE ONLY, THE ACTUAL LOCATIONS ARE TO BE DETERMINED BY THE QSP.
- 8. THE BMP'S SHOWN ON THE EROSION CONTROL PLANS ARE INTENDED AS A GUIDELINE FOR THE CONTRACTOR'S QSP, IMPLEMENTATION OF THESE OR OTHER
- BMP'S WILL BE THE RESPONSIBILITY OF THE QSP. 9. ALL ROADWAYS SHALL BE KEPT CLEAN ON A DAILY BASIS BY MEANS OF VACUUMING OR STREET SWEEPINGS.
- 10. PRIOR TO FORECAST RAIN EVENTS, THE QSP SHALL EVALUATE THE SITE AND
- ESTABLISH ADEQUATE BMP'S TO PROTECT ALL DISTURBED AREAS FROM EROSION. 11. STORM DRAIN INLET PROTECTION SHALL BE TYPE 2 DURING STORM DRAIN INSTALLATIONS, AND TYPE 3 AFTER PAVING OPERATIONS HAVE BEEN COMPLETED,
- (SEE BMP GUIDANCE HANDOUT IN THE SWPPP FOR MORE INFORMATION). 12. THE STRAW WATTLES SHOWN ON THESE PLANS ARE INTENDED TO REPRESENT DIFFERENT PHASES OF CONSTRUCTION. CONTRACTOR SHALL INCORPORATE THEIR USE AS NEEDED DURING CONSTRUCTION OR AS DIRECTED BY INSPECTOR.

EROSION CONTROL NOTES

1. THE BMP'S PROPOSED ON THESE PLANS ARE INTENDED AS A GUIDELINE FOR THE CONTRACTOR. OTHER AND/OR MORE EXTENSIVE MEASURES MAY BECOME NECESSARY DURING CONSTRUCTION, AND WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO IMPLEMENT AT NO ADDITIONAL COST TO THE CITY.


GOOD HOUSEKEEPING PRACTICES

- 1. THE CONTRACTOR SHALL CONDUCT AN INVENTORY OF THE PRODUCTS USED AND/OR EXPECTED TO BE USED AND THE END PRODUCTS THAT ARE PRODUCED AND/OR EXPECTED TO BE PRODUCED.
- 2. COVER AND BERM LOOSE STOCKPILED CONSTRUCTION MATERIALS THAT ARE NOT ACTIVELY BEING USED.
- 3. STORE CHEMICALS IN WATERTIGHT CONTAINERS (WITH APPROPRIATE SECONDARY CONTAINMENT TO PREVENT ANY SPILLAGE OR LEAKAGE) OR IN A STORAGE SHED
- 4. ALL EQUIPMENT AND VEHICLE FUELING AND MAINTENANCE PROCEDURES SHALL BE DONE IN THE AREA SHOWN ON THE SITE PLANS OR OTHER LOCATION WHERE THE APPROPRIATE BMP'S HAVE BEEN INSTALLED TO PREVENT ANY CONTAMINATION OF
- 5. THE CONTRACTOR SHALL USE SOME TYPE OF GROUND COVER OR OTHER DEVISES TO INSURE NO PETROLEUM PRODUCTS COME IN CONTACT WITH SOILS DURING FUELING AND MAINTENANCE.
- 6. THE CONTRACTOR SHALL PROVIDE APPROPRIATE CONTAINMENT AROUND ANY
- SANITARY TOILETS THAT PREVENT CONTAMINATION TO THE SOILS. 7. ANY BUILDING MATERIALS THAT ARE STORED ON-SITE THAT HAVE THE POTENTIAL TO CONTRIBUTE NON-VISIBLE POLLUTANTS TO THE STORM WATER RUNOFF SHALL BE STORED IN WATERTIGHT CONTAINERS OR UNDER THE COVER OF SHELTERS THAT
- PROVIDE PROTECTION FROM RAINS. 8. CONSTRUCTION MATERIAL WASTES SHALL BE CLEANED UP DAILY AND STORED IN COVERED CONTAINERS PRIOR TO DISPOSAL.
- 9. THE CONTRACTOR HAS THE OPTION TO USE METAL SHAKER BOARDS IN LIEU OF RIP RAP AT THE CONSTRUCTION ENTRANCE AS LONG AS IT PROVIDES ADEQUATE TIRE CLEANING ABILITIES.



PLACE NET-WRAPPED STRAW WATTLE IN TRENCH. WATTLE TO BE TIGHTLY BUTTED END TO END BUT NOT OVERLAPPING. MINIMUM 6 STAKES PER 25' OF WATTLE.

SE-5 STRAW WATTLE DETAIL



.

CRUSHED

SECTION A-A

AGGREGATE

GREATER THAN 3"


BUT SMALLER THAN

ORIGINAL

GRADE

10 ML

STEEL WIRE



OR (4x) THE CIRCUMFERENCE DITCH

OF THE LARGEST

CONSTRUCTION VEHICLE TIRE,


WHICHEVER IS GREATER.

SPILL WAY, -1-BAG HIGH TYPICAL PROTECTION FOR INLET ON **GRADE** -NTS-

1. INTENDED FOR SHORT TERM USE USE TO INHIBIT NON-STORM WATER FLOWS ALLOW FOR PROPER MAINTENANCE AND CLEANUP 4. BAGS MUST BE REMOVED AFTER ADJACENT OPERATION IS

COMPLETE 5. NOT APPLICABLE IN AREAS WITH HIGH SILTS & WITHOUT FILTER FABRIC

SE-10 STORM DRAIN INLET PROTECTION TYPE-3



SE-10 STORM DRAIN INLET PROTECTION TYPE-3 -NTS-


MATCH EXISTING GRADE TC-1 STABLIZED CONSTRUCTION ENTRANCE/EXIT -NTS-CURB & GUTTER -FLOW -GRAVEL BAGS 50' O/C TYP. IN FLOW LINES OF GUTTER

SE-6 GRAVEL BAGS IN FLOW LINE DETAIL

rrmdesign.com | (510) 751-4910 325 Davis St. San Leandro, CA 94577



RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION



eley, 4 **OV** Berke 200

Z

ш

△

O

2

A A

 \mathbb{A} \vdash ZW Way, King S M 2 N 山乙


DATE NO. REVISION COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218

PROJECT MANAGER DRAWN BY CHECKED BY

NOVEMBER 22, 2022 PROJECT NUMBER 2211-01-RC21

SHEET


SET BID







RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION



ARK EROSION

NO. REVISION COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218

NOVEMBER 22, 2022 PROJECT NUMBER

2211-01-RC21 CE101

City of Berkeley's Pollution Prevention - It's Part of the Plan


Make sure your crews and subs do the job right!

Runoff from streets and other paved areas is a major source of pollution and damage to creeks and the San

and crews plan ahead to keep dirt, debris, and other construction waste away from storm drains and local

creeks. Following these guidelines and the project specifications will ensure your compliance with City of

Francisco Bay. Construction activities can directly affect the health of creeks and the Bay unless contractors



Materials storage & spill cleanup

Non-hazardous materials management

- ✓ Sand, dirt, and similar materials must be stored at least 10 feet (3 meters) from catch basins. All construction material must be covered with a tarp and contained with a perimeter control during wet weather or when rain is forecasted or when not actively being used within 14 days.
- Use (but don't overuse) reclaimed water for dust control as needed.
- ✓ Sweep or vacuum streets and other paved areas daily. Do not wash down streets or
- Recycle all asphalt, concrete, and aggregate base material from demolition activities. Comply with City of Berkeley Ordinances for recycling construction materials, wood, gyp board, pipe, etc.
- ► Check dumpsters regularly for leaks and to make sure they are not overfilled. Repair or replace leaking dumpsters promptly.
- Cover all dumpsters with a tarp at the end of every work day or during wet weather.

Hazardous materials management

- Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with city, county, state, and federal regulations.
- ✓ Store hazardous materials and wastes in water tight containers, store in appropriate secondary containment, and cover them at the end of every work day or during wet weather or when rain is forecasted.
- Follow manufacturer's application instructions for hazardous materials and be careful not to use more than necessary. Do not apply chemicals outdoors when rain is forecasted within 24 hours.
- ▶ Be sure to arrange for appropriate disposal of all hazardous wastes.

Spill prevention and control

- ✓ Keep a stockpile of spill cleanup materials (rags, absorbents, etc.) available at the construction site at all times.
- ✓ When spills or leaks occur, contain them immediately and be particularly careful to prevent leaks and spills from reaching the gutter, street, or storm drain. Never wash spilled material into a gutter, street, storm drain, or creek!
- Dispose of all containment and cleanup materials properly.
- Report any hazardous materials spills immediately! Dial 911 or
- the City of Berkeley's Public Works Department by dialing 311

Construction Entrances and Perimeter

- Establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from site
- ✓ Sweep or vacuum any street tracking immediately and secure sediment source to prevent further tracking.

Vehicle and equipment maintenance & cleaning

Berkeley requirements.

- Inspect vehicles and equipment for leaks frequently. Use drip pans to catch leaks until repairs are made; repair leaks promptly.
- Fuel and maintain vehicles on site only in a bermed area or over a drip pan that is big enough to prevent runoff.
- ✓ If you must clean vehicles or equipment on site, clean with water only in a bermed area that will not allow rinse water to run into gutters, streets,
- storm drains, or creeks. → Do not clean vehicles or equipment
- on-site using soaps, solvents, degreasers, steam cleaning equipment, etc.

Earthwork & contaminated soils

- ✓ Keep excavated soil on the site where it will not collect in the street.
- Transfer to dump trucks should take place on the site, not in the street.
- ✓ Use fiber rolls, silt fences, or other control measures to minimize the flow of silt off the site.



- Earth moving activities are only allowed during dry weather by permit and as approved by the City Inspector in the Field. ✓ Mature vegetation is the best form of erosion control. Minimize disturbance to
- existing vegetation whenever possible. If you disturb a slope during construction, prevent erosion by securing the soil with erosion control fabric, or seed with fastgrowing grasses as soon as possible. Place fiber rolls down-slope until soil is secure.
- ✓ If you suspect contamination (from site history, discoloration, odor, texture, abandoned underground tanks or pipes, or buried debris), call the Engineer for help in determining what should be done, and manage disposal of entaminated soil according to their instructions.

Architectural Copper

If project contains architectural copper use best management practices as detailed in the handout Requirements for Architectural Copper available at the lobby of the Permit Service Center.

Dewatering operations

- Effectively manage all run-on, all runoff within the site, and all runoff that discharges from the site. Run-on from off site shall be directed away from all disturbed areas or shall collectively be in compliance.
- Reuse water for dust control, irrigation, or another on-site purpose to the greatest extent possible.
- ▶ Be sure to notify and obtain approval from the Engineer before discharging water to a street, gutter, or storm drain. Filtration or diversion through a basin, tank, or sediment trap may be required.
- ✓ In areas of known contamination, testing is required prior to reuse or discharge of groundwater. Consult with the Engineer to determine what testing is required and how to interpret results. Contaminated groundwater must be treated or hauled off-site for proper disposal.

Saw cutting

- ✓ Always completely cover or barricade storm drain inlets when saw cutting. Use
- filter fabric, catch basin inlet filters, or sand/gravel bags to keep slurry out of the storm drain system.
- Shovel, absorb, or vacuum saw-cut slurry and pick up all waste as soon as you are finished in one location or at the end of each work day (whichever is
- ✓ If saw cut slurry enters a catch basin, clean it up immediately.

Paving/asphalt work



- ✓ Always cover storm drain inlets and manholes when paving or applying seal coat, tack coat, slurry seal, or fog seal.
- ▶ Protect gutters, ditches, and drainage courses with sand/gravel bags, or earthen berms. ✓ Do not sweep or wash down excess sand
- from sand sealing into gutters, storm drains, or creeks. Collect sand and return it to the stockpile, or dispose of it as trash. ✓ Do not use water to wash down fresh asphalt concrete pavement.

Concrete, grout, and mortar storage & waste disposal

- ✓ Store concrete, grout, and mortar under cover, on pallets, and away from drainage areas. These materials must never reach a storm drain.
- areas that will not allow discharge of wash water onto the underlying soil or onto the surrounding areas.



Painting

► Never rinse paint brushes or

materials in a gutter or street!

paint before rinsing brushes,

rollers, or containers in a sink.

✓ Paint out excess water-based

Collect the wash water from washing exposed aggregate concrete and remove it for appropriate disposal off site.

TO THE REAL PROPERTY OF THE PR	
V	

▶ Paint out excess oil-based paint before cleaning brushes in thinner. Filter paint thinners and solvents for reuse whenever possible. Dispose of oil-based paint sludge and unusable thinner as hazardous waste.

Landscape Materials

- Contain, cover, and store on pallets all stockpiled landscape materials (mulch, compost, fertilizers, etc.) during wet weather or when rain is forecasted or when not actively being used within 14 days.
- ✓ Discontinue the application of any erodible landscape material within 2 days of forecasted rain and during wet weather.

For references and more detailed information: www.cleanwaterprogram.org www.cabmphandbooks.com

			DATE	
			ВУ	
REVISIONS			DESCRIPTION	

				DESCR	
S	A	€	\otimes	NO.	

	€	\blacksquare	€	\triangleleft	\triangleleft	10000
Q						
PPROVED						
ā.						

APPROVED		
SENCY		

WORKS A
PUBLIC

WOR		
UBLIC		
ک P ا	-	L
124		

OF BERKEL

CITY

CIFICATION NO.

2 OF

<u>C</u>	
BL	
□	
☆	

		4
		Δ
		Щ
400 400		>
EVENTION		
\succeq		2
z		C
Æ		

OLLUTION

NO.	REVISION	DAT

Berke

Ш

S

BM

FIELD

AYGROUI

rrmdesign.com | (510) 751-4910 325 Davis St. San Leandro, CA 94577

rrm IS a California Corporation

PROJECT MANAGER DRAWN BY CHECKED BY

NOVEMBER 22, 2022


2211-01-RC21

3ID

PROJECT NUMBER

CBMP00


Storm drain polluters may be liable for fines of \$10,000 or more per day!







RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION




REN

GROVE PARI

ARK

NO.	REVISION		DATE
\triangle			
\triangle			
\triangle			
	DB SPECIFICATION PLAN NO. 825		
PROJ	ECT MANAGER		
JS			
	VN BY	CHECKED B	Υ
SC/F		DC	
DATE			
NO.	VEMBER 22, 2	2022	
PROJ	ECT NUMBER		
	2011 0		1
	2211-0	1-Kしと	l


CG101







RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION




REN

ARK

GRO

NO.	REVISION		DATE
	OB SPECIFICATION Y PLAN NO. 825		
PROJ	ECT MANAGER		
			o V
JS	VNI RV		
JS DRAV	VN BY RP	DC) i
JS	RP		
JS DRAV SC/F DATE	RP	DC	• i
JS DRAV SC/F DATE	RP	DC	• · · · · · · · · · · · · · · · · · · ·







RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION



Way, Berke FIELD DR. RG REN **AYGROUND**

ARK


GROVE

NO. REVISION COB SPECIFICATION NO. 22-11538-C

CITY PLAN NO. 8256 FILE NO. 406-218 **PROJECT MANAGER**

DRAWN BY CHECKED BY


NOVEMBER 22, 2022 PROJECT NUMBER







RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION



N/A

STORMW

ARK


NO.	REVISION	DATE
CC	DB SPECIFICATION NO. 22-11	538-C

CITY PLAN NO. 8256 FILE NO. 406-218 PROJECT MANAGER

CHECKED BY

NOVEMBER 22, 2022 PROJECT NUMBER


2211-01-RC21







RRM IS A CALIFORNIA CORPORATION




RENO

NO. REVISION

	7			
	7			
	7			
	7			
	7			
	7			
		DB SPECIFICATION Y PLAN NO. 825		
PR	O]	ECT MANAGER		
_JS				
		4/3 L B3/	A	

DRAWN BY CHECKED BY

NOVEMBER 22, 2022 PROJECT NUMBER



Point Table

2139047.0673 | 6050146.1779

2139063.5149 | 6050128.0837

2139048.0387 | 6050157.5653

2139041.0304 6050158.6333

2139069.4420 | 6050154.8408

2139070.1401 6050159.3204

2139098.2102 | 6050155.2008

2139097.1557 6050148.4489

2139099.9677 6050148.6633

2139102.6502 6050147.6956

2139148.5655 | 6050127.1297

2139150.5941 6050133.1013

2139176.5699 6050120.7162

2139179.4851 6050119.5424

2139195.0081 6050112.7066

2139215.0931 6050104.2319

2139215.4136 6050105.8758

2139313.4594 6050087.5038

2139186.2763 6049834.1492

Point # Raw Description Northing

INFIELD

CONC

FENCE

67

	Point Table				
Point #	Raw Description	Northing	Easting		
21	POST	2139039.7687	6050101.3058		
22	CONC	2139036.7301	6050061.4889		
23	CONC	2139026.0960	6050063.0520		
24	CONC	2139028.4290	6050078.4307		
25	CONC	2139039.0715	6050076.8349		
26	CONC	2139309.2453	6050086.2587		
27	CONC	2139313.0910	6050085.5380		
28	CONC	2139282.6487	6049874.6590		
29	CONC	2139283.4470	6049880.1760		
30	CONC	2139278.6837	6049880.8726		
31	CONC	2139277.8760	6049875.3496		
32	CONC	2139281.2815	6049865.0164		
33	CONC	2139276.4989	6049865.7580		
34	CONC	2139271.1710	6049866.5200		
35	INFIELD	2139044.9424	6050050.0988		
36	CONC	2139191.9780	6049871.8150		
37	CONC	2139187.3070	6049868.3820		
38	CONC	2139187.9615	6049872.4123		
39	CONC	2139188.2495	6049878.3793		
40	CONC	2139181.9598	6049879.2740		

Point Table					
Point #	Raw Description	Northing	Easting		
81	FENCE	2139195.3380	6049867.2040		
82	FENCE	2139259.3878	6049857.9380		
83	FENCE	2139265.6377	6049849.1486		
84	PLAY	2139263.4995	6049780.6248		
85	PLAY	2139265.2280	6049823.3689		
86	PLAY	2139275.6838	6049840.1997		
87	POST	2139045.0608	6050135.7641		
88	INFIELD	2139024.4381	6049922.0543		
89	POST	2139069.4367	6050153.2181		
90	POST	2139100.8007	6050146.9886		
91	PLAY	2139254.8362	6049848.5951		
92	PLAY	2139251.2847	6049837.2103		
93	PLAY	2139229.8151	6049838.0127		
94	PLAY	2139230.6934	6049854.6597		
95	PLAY	2139216.2579	6049854.6917		
96	PLAY	2139205.0732	6049856.7025		
97	PLAY	2139198.0070	6049857.6160		
98	INFIELD	2139274.1836	6049886.3506		
99	INFIELD	2139122.3618	6050116.3772		
100	INFIELD	2139051.8083	6050069.2369		

Point #	Raw Description	Northing	Easting
81	FENCE	2139195.3380	6049867.2040
82	FENCE	2139259.3878	6049857.9380
83	FENCE	2139265.6377	6049849.1486
84	PLAY	2139263.4995	6049780.6248
85	PLAY	2139265.2280	6049823.3689
86	PLAY	2139275.6838	6049840.1997
87	POST	2139045.0608	6050135.7641
88	INFIELD	2139024.4381	6049922.0543
89	POST	2139069.4367	6050153.2181
90	POST	2139100.8007	6050146.9886
91	PLAY	2139254.8362	6049848.595
92	PLAY	2139251.2847	6049837.2103
93	PLAY	2139229.8151	6049838.0127
94	PLAY	2139230.6934	6049854.6597
95	PLAY	2139216.2579	6049854.6917
96	PLAY	2139205.0732	6049856.7025
97	PLAY	2139198.0070	6049857.6160
98	INFIELD	2139274.1836	6049886.3506
99	INFIELD	2139122.3618	6050116.3772
100	INFIELD	2139051.8083	6050069.2369

	80 FENCE		2139190.8630	6049864.5960			
1							
		Poir	nt Table				
	Point #	Raw Description	Northing	Easting			
	121	GATE	2139015.0320	6049927.0925			
		<u> </u>	<u> </u>				

	Poir	nt Table	
Point #	Raw Description	Northing	Easting
41	CONC	2139183.4386	6049889.6693
42	CONC	2139189.6983	6049888.7619
43	CONC	2139157.1420	6049876.5390
44	CONC	2139158.0529	6049882.6639
45	CONC	2139283.3434	6049818.1953
46	CONC	2139290.6640	6049817.1830
47	CONC	2139292.0133	6049826.1813
48	CONC	2139284.6404	6049827.2388
49	POST	2139013.2525	6049911.9078
50	POST	2139032.5751	6049908.9193
51	POST	2139051.3697	6049906.2343
52	POST	2139069.6320	6049903.8640
53	POST	2139089.4880	6049901.1030
54	POST	2139107.7673	6049898.4948
55	POST	2139127.8070	6049895.9620
56	POST	2139145.9690	6049893.4300
57	INFIELD	2139087.0851	6050092.8070
58	CONC	2139037.3334	6050135.3799
59	INFIELD	2139042.7546	6050038.0695
60	INFIELD	2139058.9170	6050120.3469

Point Table				
Point #	Raw Description	Northing	Easting	
101	CONC	2139289.4930	6049849.2610	
102	CONC	2139287.8359	6049849.5179	
103	CONC	2139293.6258	6049878.7302	
104	CONC	2139277.2971	6049853.4722	
105	CONC	2139025.3171	6050058.0999	
106	CONC	2139019.2743	6050059.0504	
107	CONC	2139023.1943	6050084.2985	
108	CONC	2139029.1787	6050083.3732	
109	CONC	2139149.8809	6050130.9163	
110	CONC	2139174.1223	6050115.2873	
111	CONC	2139175.8054	6050118.9158	
112	CONC	2139029.7267	6050027.9281	
113	CONC	2139023.7919	6050028.8107	
114	CONC	2139024.8216	6050035.7346	
115	CONC	2139030.7564	6050034.8520	
116	CONC	2139031.0726	6050036.9789	
117	CONC	2139025.1379	6050037.8615	
118	CONC	2139026.1676	6050044.7853	
119	CONC	2139032.1023	6050043.9027	
120	GATE	2139014.4090	6049923.1410	

NOTE


AN ENGINEERING PERMIT WILL BE REQUIRED FOR ANY WORK IN THE PUBLIC RIGHT-OF-WAY, INCLUDING BUT NOT LIMITED TO CONSTRUCTION STAGING, CONSTRUCTION PARKING, SIDEWALK, SHORING, DRAINAGE, OR SEWER WORK. THE ENGINEERING PERMIT CAN BE ISSUED AFTER THE BUILDING PERMIT IS APPROVED OR ISSUED. APPROVAL OF THIS BUILDING PERMIT DOES NOT AUTHORIZE WORK IN THE RIGHT-OF-WAY.



rrmdesign.com | (510) 751-4910 325 Davis St. San Leandro, CA 94577



RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION



PARK FIELD ANI ND RENOVATION Jr. Way, Berkeley, C


HORIZONTAL POINT

NO. REVISION

COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218 PROJECT MANAGER

DRAWN BY CHECKED BY SC/RP


NOVEMBER 22, 2022 PROJECT NUMBER







RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION




, Berkeley, FIELD REN CONSTRUCTIO ARK GROVE PARK
PLAYGROUND R
828 Martin Luther King Jr. V

NO. REVISION DATE COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218

PROJECT MANAGER

DRAWN BY CHECKED BY

NOVEMBER 22, 2022 PROJECT NUMBER



MATERIALS LEGENID

SYMBOL	TYPE	DESCRIPTION	DETAIL(S)
xxxx	FENCE - TYPE 1	42" HIGH CHAIN LINK FENCE, SEE SPECS	1 LC502
— //	FENCE - TYPE 2	5'-0" HIGH CHAIN LINK FENCE, SEE SPECS	7 LC502
	FENCE - TYPE 3	10'-0" HIGH CHAIN LINK FENCE, SEE SPECS	1 LC503
	FENCE - TYPE 4	16'-0" HIGH CHAIN LINK FENCE, SEE SPECS	1 LC504
0000	PROPOSED NETTING	SEE SPECIFICATIONS	
	REDWOOD HEADER	SEE SPECIFICATIONS	9 LC501
	CONCRETE WALL	CONCRETE CURB WALL OR RETAINING WALL - SEE PLANS FOR TYPE	6 LC502 4 LC504
\swarrow	PROPOSED POST FOR NETTING	SEE SPECIFICATIONS	1 LC505
•	EXISTING POST FOR NETTING		
	PROPOSED NETTING OVER BACKSTOP	SEE SPECIFICATIONS	
0 0	WOOD RETAINING EDGE		6 LC504
-0 -0	EXISTING PRE-FABRICATED METAL FENCE	TO REMAIN	
-00	EXISTING CHAIN LINK FENCE	TO REMAIN	

1. SEE SHEET G002 FOR SYMBOL LEGEND.


1" = 20'

- 2. SEE CH SERIES SHEETS FOR LAYOUT PLAN.
- SEE SHEET LC101 FOR MATERIALS. 4. DIMENSIONS ON THIS PLAN ARE APPROXIMATE DISTANCES BETWEEN EXISTING
- POSTS. VERIFY ALL DIMENSIONS IN FIELD.
- 5. SEE SHEET LC401 FOR BACKSTOP AND DUGOUT ENLARGEMENT. SEE CG SERIES SHEETS FOR GRADING AND DRAINAGE PLAN.

7. SEE S SERIES SHEETS FOR STRUCTURAL NOTES AND DETAILS. 8. BALL NET POSTS AND ATTACHMENTS TO BE DEFERRED SUBMITTAL.



RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION



Berke FIELD

REN


ARK

GROVE PARI


NO.	REVISION		DATE
\triangle			
\triangle			
)B SPECIFICA Y PLAN NO. 8		
	ECT MANAGI		J. 400 Z10
JS			
DRAV	VN BY	CHECKI	ED BY
ΥI		JS	

2211-01-RC21


PROJECT NUMBER







RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION



AND ATIOI REN ARK


NO.	REVISION	DATE
\triangle		

CHECKED BY

2211-01-RC21

NOVEMBER 22, 2022 PROJECT NUMBER

AN ENGINEERING PERMIT WILL BE REQUIRED FOR ANY WORK IN THE PUBLIC RIGHT-OF-WAY, INCLUDING BUT NOT LIMITED TO CONSTRUCTION STAGING, RESERVED CONSTRUCTION PARKING, SIDEWALK, DRAINAGE, OR SEWER WORK. APPROVAL OF THIS BUILDING PERMIT DOES NOT AUTHORIZE WORK IN THE PUBLIC RIGHT-OF-WAY.



PLAY COMPONENTS AT 2-5 YR PLAY

		• • • • • • • • • • • • • • • • • • • •
	TOTAL	REQUIRED MINIMUM
ELEVATED PLAY COMPONENTS	12	FOR 11 TO 13 ELEVATED COMPONENTS
GROUND-LEVEL PLAY COMPONENTS ON ACCESSIBLE ROUTE	14	4
DIFFERENT TYPES OF GROUND-LEVEL PLAY COMPONENTS ON ACCESSIBLE ROUTE	9	9

PLAY COMPONENTS AT 5-12 YR PLAY

	TOTAL	REQUIRED MINIMUM
ELEVATED PLAY COMPONENTS	2	FOR 2 TO 4 ELEVATED COMPONENTS
GROUND-LEVEL PLAY COMPONENTS ON ACCESSIBLE ROUTE	10	1
DIFFERENT TYPES OF GROUND-LEVEL PLAY COMPONENTS ON ACCESSIBLE ROUTE	4	1

MATERIALS LEGEND

SYMBOL	<u>TYPE</u>	DESCRIPTION	DETAIL(S)
7. 7	CONCRETE STANDARD	MEDIUM BROOM FINISH, JOINTS PER PLAN	1 LC501
4 .	VEHICULAR CONCRETE	MEDIUM BROOM FINISH, JOINTS PER PLAN. SEE DETAIL	1 LC501
	CITY STANDARD CONCRETE SIDEWALK	MEDIUM BROOM FINISH, JOINTS PER PLAN. SEE DETAIL	1 LC501
	THICKENED CONCRETE EDGE	AT ALL CONCRETE PAVING EDGES ADJACENT TO NON-HARDSCAPE AREAS	3 LC501
	ENGINEERED WOOD FIBER	SEE DETAIL	4 LC501
	SAND	PLAYGROUND SAND, SEE SPECIFICATIONS.	
\(\psi \)	TURF	SEE SPECIFICATIONS. REFER TO BID ALTERNATE #1	
	PROTECTIVE RUBBER SURFACING	SEE DETAIL	11 LC501
	STABILIZED DECOMPOSED GRANITE	REFER TO NOTE ON PLAN. SEE SPECIFICATIONS.	7 LC501
++++	BALL FIELD WARNING TRACK	DECOMPOSED GRANITE, SEE DETAILS	10 LC501
En company of the com	EXISTING TREE TO REMAIN	SEE SHEET DM001 FOR TREE PROTECTION NOTES	
	EXISTING PRE-FABRICATED METAL FENCE	TO REMAIN	
-00	EXISTING CHAIN LINK FENCE	TO REMAIN	
	WOOD RETAINING EDGE		6 LC504

NOTES

PE-07

- 1. SEE SHEET G002 FOR SYMBOL LEGEND.
- SEE CH SERIES SHEETS FOR LAYOUT PLAN.
- SEE SHEET LC101 FOR MATERIALS. SEE SHEET LC102 FOR FENCE AND WALL IMPROVEMENTS.
- SEE CG SERIES SHEETS FOR GRADING AND DRAINAGE PLAN. 6. SEE S SERIES SHEETS FOR STRUCTURAL NOTES AND DETAILS.

REFERENCE NOTES


	LINCL NOTES		
SYMBOL	32 EXTERIOR IMPROVEMENTS DESCRIPTION	<u>QTY</u>	<u>DETAIL</u>
32-01	TABLE, ADA PER SPECIFICATIONS	4	6/LC508
32-02	BENCH - TYPE 1, PER SPECIFICATIONS	4	8/LC508
32-03	TRASH RECEPTACLE, PER SPECIFICATIONS	4	
32-04	BBQ GRILL, PER SPECIFICATIONS	2	
SYMBOL	PLAY EQUIPMENT DESCRIPTION	<u>QTY</u>	DETAIL
PE-01	BERLINER 5-12 YR STRUCTURE		
PE-02	BERLINER ELBOW SWING		
PE-03	BURKE STEPPING POD		
PE-04	BURKE TRACK RIDE		

LANDSCAPE STRUCTURES BUCKET SWINGS

LANDSCAPE STRUCTURES 2-5 YR STRUCTURE

LANDSCAPE STRUCTURES ROCKER

LANDSCAPE STRUCTURES FOSSIL






rrmdesign.com | (510) 751-4910 325 Davis St. San Leandro, CA 94577



RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION



FIELD N N N REN


R


NO. REVISION

COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218

CHECKED BY

NOVEMBER 22, 2022 PROJECT NUMBER 2211-01-RC21





RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION



Berke Z W Way, ~ NSTRU GR

DATE NO. REVISION COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218


PROJECT MANAGER

DRAWN BY CHECKED BY


NOVEMBER 22, 2022 PROJECT NUMBER 2211-01-RC21

SHEET


SEI








RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION




Berke RENGY. NSTRU

DATE NO. REVISION COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218 **PROJECT MANAGER** DRAWN BY CHECKED BY


NOVEMBER 22, 2022 PROJECT NUMBER 2211-01-RC21








RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION



Berkeley, FIELD REN R OUND ONSTRU Q R

NO. REVISION DATE COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218 **PROJECT MANAGER** DRAWN BY CHECKED BY NOVEMBER 22, 2022


> PROJECT NUMBER 2211-01-RC21








RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION



Berke FIELD REN **X** OUND ONSTRU

NO. REVISION DATE COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218 **PROJECT MANAGER** DRAWN BY CHECKED BY


NOVEMBER 22, 2022 PROJECT NUMBER







RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION




Berkeley, FIELD REN ARK OUND ONSTRU


DATE NO. REVISION COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218 **PROJECT MANAGER**


DRAWN BY CHECKED BY

NOVEMBER 22, 2022 PROJECT NUMBER

2211-01-RC21 SHEET








SIDEWALK DRAIN STANDARD DETAIL

CITY OF BERKELEY TRENCH BACKFILL & RESURFACING STANDARD DETAIL



DRAWN: HEI

SCALE: _____

CITY OF BERKELEY SIDEWALK STANDARD DETAIL

rrmdesign.com | (510) 751-4910 325 Davis St. San Leandro, CA 94577



OR SPECIFICATIONS SHALL CONSTITUTE CONCLUMENTS FOR PUBLIC AGENCY REVIEW SHALL NOT BE CONSIDERED A WAIVER OF RRM DESIGN GROUP'S RIGHTS. RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION



03 Berkeley, 4 FIELD Z W NSTRU


4

R GR


NO.	REVISION	1		DATE
			_	
	B SPECIFIC PLAN NO			
PROJE	ECT MANA	GER		
JS				
DRAW	/N BY		CHECKED) BY
DATE			JS	
NOVEMBER 22, 20		22		


BID


SET




\ EXISTING STORM DRAIN CONNECTION DETAIL











FRENCH DRAIN DETAIL



CITY OF BERKELEY CURB AND GUTTER STANDARD DETAIL






rrmdesign.com | (510) 751-4910 325 Davis St. San Leandro, CA 94577



RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION



OV Berke Z S

NO. REVISION DATE COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218 **PROJECT MANAGER** DRAWN BY CHECKED BY


NOVEMBER 22, 2022 PROJECT NUMBER 2211-01-RC21

SHEET


SET

BID


FILE: 20B-156 SHEET: 1 OF 1







RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION



Berkeley, ONSTRUCTION REN King Jr. OUND

NO. REVISION COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218 **PROJECT MANAGER** DRAWN BY CHECKED BY

NOVEMBER 22, 2022 PROJECT NUMBER 2211-01-RC21

STRUCTURAL OBSERVATIONS

A. FOUNDATION REINFORCING

- 1. IN ACCORDANCE WITH SECTION 1704.6 OF THE CODE STRUCTURAL OBSERVATIONS SHALL BE PERFORMED FOR THE FOLLOWING ELEMENTS OF CONSTRUCTION:
- THE OBJECTIVE OF THE STRUCTURAL OBSERVATION IS TO BECOME FAMILIAR WITH THE PROGRESS AND QUALITY OF THE CONTRACTOR'S WORK AND DETERMINE IF THE WORK IS BEING COMPLETED IN GENERAL CONFORMANCE WITH THE APPROVED PLANS AND SPECIFICATIONS
- A. STRUCTURAL OBSERVATIONS ARE NOT INSPECTIONS AND SHALL NOT BE USED AS A REPLACEMENT FOR THE SPECIAL INSPECTIONS REQUIRED BY THE CODE OR REFERENCED STANDARD OR FOR SPECIAL INSPECTIONS REQUIRED IN THIS DOCUMENT.
- B. THE PERSON COMPLETING THE STRUCTURAL OBSERVATIONS DOES NOT HAVE RESPONSIBILITY FOR ANY ACTS OR OMISSIONS BY THE CONTRACTOR OR OF ANY OTHER ENTITY PROVIDING MATERIALS OR SERVICES ON THE PROJECT.
- ADEQUATE NOTIFICATION SHALL BE PROVIDED TO THE STRUCTURAL ENGINEER PERFORMING OBSERVATIONS, A MINIMUM OF (2) WORKING DAYS, PRIOR TO OBSERVATION OF THE WORK.

STATEMENT OF SPECIAL INSPECTIONS

THIS STATEMENT OF SPECIAL INSPECTIONS HAS BEEN PREPARED PURSUANT TO SECTION 1704.3 OF THE CODE. THIS SECTION DETAILS BOTH REQUIRED SPECIAL INSPECTIONS AND TESTS INCLUDING TESTING PER SECTION 1705 OF THE CODE. THE FOLLOWING SHALL BE OBSERVED DURING THEIR IMPLEMENTATION:

A. GENERAL:

a. Structural verifications, inspections and tests shall be performed in accordance WITH CHAPTER 17 OF THE CODE AND/OR THE APPLICABLE REFERENCE STANDARD.

B. OWNER REQUIREMENTS:

a. THE OWNER OR OWNER'S AGENT SHALL EMPLOY ONE OR MORE APPROVED AGENCIES TO PERFORM INSPECTIONS DURING CONSTRUCTION ON THE TYPES OF WORK LISTED IN SECTION 1705 OF THE CODE AND IN THIS STATEMENT OF INSPECTIONS.

C. SPECIAL INSPECTOR QUALIFICATIONS:

a. THE SPECIAL INSPECTIONS SHALL PROVIDE WRITTEN DOCUMENTATION TO THE BUILDING OFFICIAL DEMONSTRATING HIS OR HER COMPETENCE AND RELEVANT EXPERIENCE OR TRAINING. THE EXPERIENCE OR TRAINING SHALL BE CONSIDERED RELEVANT WHEN THE DOCUMENTED EXPERIENCE OR TRAINING IS RELATED IN COMPLEXITY TO THE SAME TYPE OF SPECIAL INSPECTION ACTIVITIES FOR PROJECTS OF SIMILAR COMPLEXITY AND MATERIAL

D. CONTRACTOR REQUIREMENTS:

- a. SPECIAL INSPECTION IS IN ADDITION TO THE CONTRACTOR'S QUALITY CONTROL INSPECTIONS AND TESTING. THE CONTRACTOR'S QUALITY CONTROL INSPECTIONS AND TESTING SHALL OCCUR PRIOR TO SPECIAL INPECTION AND REPORTS SHALL BE AVAILABLE TO THE SPECIAL
- b. THE CONTRACTOR SHALL ENSURE THAT THE WORK FOR WHICH SPECIAL INSPECTION IS REQUIRED REMAINS ACCESSIBLE AND EXPOSED FOR SPECIAL INSPECTION PURPOSES UNTIL COMPLETION OF THE REQUIRED SPECIAL INSPECTION.
- c. ANY CONTRACTOR RESPONSIBLE FOR THE CONSTRUCTION OF THE MAIN WIND OR SEISMIC FORCE RESISTING SYSTEM SHALL SUBMIT A WRITTEN STATEMENT OF RESPONSIBILITY TO THE BUILDING OFFICIAL AND OWNER PRIOR TO COMMENCEMENT OF WORK ON THE SYSTEM OR COMPONENT. THE STATEMENT OF RESPONSBILITY SHALL CONTAIN ACKNOWLEDGEMENT OF AWARENESS OF THE SPECIAL INSPECTION REQUIREMENTS CONTAINED IN THE STATEMENT OF SPECIAL INSPECTIONS.

E. SPECIAL INSPECTOR REPORT REQUIREMENTS:

- a. THE SPECIAL INSPECTOR SHALL KEEP RECORD OF INSPECTIONS
- b. THE SPECIAL INPSECTOR SHALL FURNISH INSPECTION REPORTS TO THE BUILDING OFFICIAL AND TO THE ARCHITECT AND ENGINEER OF RECORD.
- . REPORTS SHALL INDICATE THAT WORK INSPECTED WAS OR WAS NOT COMPLETED IN CONFORMANCE TO APPROVED CONSTRUCTION DOCUMENTS.
- d. DISCREPANCIES SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE CONTRACTOR FOR
- e. IF NOT CORRECTED DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE BUILDING OFFICIAL AND THE ARCHITECT AND ENGINEER OF RECORD PRIOR TO THE COMPLETION OF THAT
- f. A FINAL REPORT DOCUMENTING SPECIAL INSPECTIONS AND CORRECTION OF ANY DISCREPANCIES NOTED SHALL BE SUBMITTED TO THE BUILDING OFFICIAL.

SUBMITTALS

- 1. THE FOLLOWING SUBMITTALS SHALL BE SUBMITTED FOR REVIEW AND APPROVAL BY THE ENGINEER:
- A. STEEL INCLUDING MISC. METALS a. SHOP DRAWINGS FOR FABRICATION AND ERECTION
 - b. WPS's (INCLUDING PQR'S AS APPLICABLE)
 - c. REINFORCING STEEL
- a. SHOP DRAWINGS FOR FABRICATION AND PLACEMENT
- BEFORE SUBMITTING EACH SUBMITTAL, (INCLUDES SHOP DRAWINGS, PRODUCT DATA, SAMPLES AND SIMILAR SUBMITTALS), THE CONTRACTOR SHALL HAVE: A. REVIEWED AND COORDINATED EACH SUBMITTAL WITH OTHER SUBMITTALS AND WITH THE REQUIREMENTS
- OF THE WORK AND THE CONTRACT DOCUMENTS. THIS INCLUDES THE CONTRACTOR REVIEWING AND VERIFYING THAT THE SUBMITTAL IS COORDINATED AMONG ALL CONSTRUCTION TRADES:
- B. DETERMINED AND VERIFIED ALL FIELD MEASUREMENTS, QUANTITIES, DIMENSIONS, SPECIFIED PERFORMANCE AND DESIGN CRITERIA, INSTALLATION REQUIREMENTS, MATERIALS, CATALOG NUMBERS AND SIMILAR INFORMATION
- C. DETERMINED AND VERIFIED ALL INFORMATION RELATIVE TO THE CONTRACTOR'S RESPONSIBILITIES FOR MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES OF CONSTRUCTION, AND SAFETY PRECAUTIONS AND PROGRAMS.
- D. REVIEWED AND VERIFIED THAT THE ARCHITECT'S OR ENGINEER'S COMMENTS FROM PREVIOUS SUBMITTAL ROUNDS HAVE BEEN ADDRESSED.
- EACH SUBMITTAL SHALL BEAR A STAMP OR SPECIFIC WRITTEN CERTIFICATION THAT THE CONTRACTOR HAS SATISFIED THEIR OBLIGATIONS UNDER THE CONTRACT DOCUMENTS WITH RESPECT TO THE CONTRACTOR'S REVIEW AND APPROVAL OF THAT SUBMITTAL.
- THE CONTRACTOR'S OBLIGATION TO PERFORM AND COMPLETE THE WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS SHALL BE ABSOLUTE:
 - a. REVIEW AND APPROVAL OF SHOP DRAWINGS BY THE ARCHITECT AND/OR ENGINEER DOES NOT CONSTITUTE APPROVAL OF A CHANGE REQUEST, SUBSTITUTION OR MODIFICATION TO THE CONTRACT DRAWINGS.
 - b. THE ARCHITECT AND ENGINEER SHALL BE NOTIFIED OF CHANGE REQUESTS, SUBSTITUTIONS OR MODIFICATIONS TO THE CONTRACT DRAWINGS IN WRITING BEFORE AND SEPARATE FROM THE SUBMITTAL PRIOR TO SUBMISSION.
- FABRICATION FOR ITEMS IN THESE DOCUMENTS SHALL NOT COMMENCE UNTIL THE SUBMITTAL HAS BEEN REVIEWED AND APPROVED BY THE ENGINEER.

REINFORCING STEEL

- REINFORCING BARS SHALL CONFORM TO THE REQUIREMENTS OF CHAPTER 19 OF THE CODE AND WITH THE PROVISIONS OF ACI 318-14, ASTM A706, GRADE 60 UNO. ASTM A615 GR 60 STEEL MAY BE SUBSTITUTED FOR ASTM A706 GR60 STEEL PER ACI 318-14 SECTION 20.2.2.5 PROVIDED THE FOLLOWING CONDITIONS ARE MET:
- A. THE ACTUAL YIELD STRENGTH BASED ON MILL TESTS DOES NOT EXCEED THE SPECIFIED YIELD STRENGTH BY MORE THAN 18,000 PSI.
- B. THE RATIO OF THE ACTUAL ULTIMATE TENSILE STRESS TO THE ACTUAL YIELD STRENGTH IS NOT LESS THAN
- C. WHERE REINFORCEMENT COMPLYING WITH ASTM A615 IS TO BE WELDED, CHEMICAL TESTS SHALL BE PERFORMED TO DETERMINE WELDABILITY IN ACCORDANCE WITH SECTION 26.6.4 OF ACI 318-14.
- 2. BARS SHALL BE CLEAN OF RUST, GREASE, OR OTHER MATERIALS LIKELY TO IMPAIR BOND. ALL REINFORCING BAR BENDS SHALL BE MADE COLD.
- 3. WELDED WIRE REINFORCEMENT (WWR), PLAIN OR DEFORMED, SHALL CONFORM TO ASTM A185. WELDED DEFORMED WIRE REINFORCEMENT (WWR) SHALL CONFORM TO ASTM A 1064. ALL WWR FOR STAIR PANS AND ALL WWR FOR CONCRETE FILL ON METAL DECK TO BE PLAIN WWR, PROVIDE LAPS PER ACI 318-14 SECTION 25.5.3 OR 25.5.4 MINIMUM. WWR SHALL BE SUPPORTED ON APPROVED CHAIRS.
- REINFORCING BAR LAP SPLICES SHALL BE MADE AS INDICATED ON THE DRAWINGS. LAP ALL HORIZONTAL BARS AT CORNERS AND INTERSECTIONS. STAGGER ALL SPLICES UNLESS NOTED OTHERWISE ON PLANS.
 - A. MINIMUM LAP SPLICE LENGTH FOR REINFORCING STEEL BARS IN CONCRETE SHALL BE PER ACI 318-14 SECTION 25.5.2 AND THE REINFORCING SCHEDULE ON THE DRAWINGS.
 - B. MINIMUM LAP SPLICE LENGTH FOR REINFORCING STEEL BARS IN MASONRY SHALL BE PER ACI 530-13 SECTION 8.1.6.7.1 OR 9.3.3.4 AND THE REINFORCING SCHEDULE ON THE DRAWINGS.
- ALL BARS SHALL BE MARKED SO THEIR IDENTIFICATION CAN BE MADE WHEN THE FINAL IN-PLACE INSPECTION IS MADE. ALL REINFORCING CONFORMING TO DIFFERING ASTM SPECIFICATIONS AND/OR OF DIFFERING GRADES SHALL BE CLEARLY MARKED TO DIFFERENTIATE THEM FROM OTHER REINFORCING STEEL IF CONCURRENTLY PRESENT ON SITE.
- WHERE WELDING OF REINFORCING IS APPROVED BY THE STRUCTURAL ENGINEER, IT SHALL BE DONE BY AWS CERTIFIED WELDERS USING E80XX OR APPROVED ELECTRODES. WELDING PROCEDURES SHALL CONFORM TO THE REQUIREMENTS OF STRUCTURAL WELDING CODE- REINFORCING STEEL", AWS-D1.4-15. REINFORCING BARS TO BE WELDED SHALL CONFORM TO THE REQUIREMENTS OF ASTM A706.
- REINFORCING STEEL SHALL BE ACCURATELY PLACED AND ADEQUATELY SUPPORTED BEFORE THE CONCRETE IS PLACED AND SHALL BE SECURED AGAINST DISPLACEMENT DURING CONSTRUCTION WITHIN PERMITTED TOLERANCES. ADEQUATE SUPPORTS ARE ALSO NECESSARY TO KEEP THE REINFORCING STEEL AT THE PROPER DISTANCE FROM THE FORMS. USE WIRE BAR SUPPORTS, PRECAST CONCRETE SUPPORTS, SPACERS, BOLSTERS, REINFORCEMENT OR OTHER MEANS OF SUPPORT PER THE "CRSI MANUAL OF STANDARD PRACTICE", LATEST
- REINFORCING STEEL SHALL BE DETAILED IN ACCORDANCE WITH THE "CRSI MANUAL OF STANDARD PRACTICE FOR DETAILING REINFORCED CONCRETE STRUCTURES", LATEST EDITION.
- 9. COMPLETE AND DETAILED REINFORCING PLACEMENT DRAWINGS SHALL BE PREPARED AND SUBMITTED TO THE ARCHITECT FOR APPROVAL BY THE SEOR PRIOR TO FABRICATION IN ACCORDANCE WITH THE SPECIFICATIONS AND APPLICABLE CODES. THESE DRAWINGS SHALL BE AVAILABLE ON THE JOB SITE PRIOR TO PLACING OF CONCRETE. THE REINFORCING PLACEMENT DRAWINGS SHALL INCLUDE ALL PRIMARY REINFOREMENT, LAP SPLICES, TIES, DOWELS, HEADED U-DOWELS, EMBED PLATES, ANCHOR BOLTS, ETC. AREAS OF CONGESTION SHALL BE DETAILED SUFFICIENTLY TO DEMONSTRATE THAT PLACEMENT OF REBAR MEETS SPACING REQUIREMENTS OF ACI 318-14.
- 10. MILL TEST REPORTS FOR GRADE 60 BARS SHALL BE SUBMITTED TO THE INSPECTOR OF RECORD PRIOR TO PLACEMENT OF CONCRETE PER ACI 318-14 SECTION 26.13.2.3 OF THE CODE.
- 11. WHEN REQ'D, INSPECTION OF CONCRETE SHALL INCLUDE INSPECTION DURING INSTALLATION OF REINFORCING STEEL. INSPECTION SHALL BE SCHEDULED SO THAT PLACEMENT OF REINFORCING STEEL, CONDUIT, SLEEVES, AND EMBEDDED ITEMS MAY BE CORRECTED PRIOR TO PLACEMENT OF OVERLYING GRIDS
- 12. CONCRETE PROTECTION FOR REINFORCEMENT

THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCEMENT IN CAST-IN-PLACE CONCRETE (NON-PRESTRESSED):		MINIMUM COVER, IN.
A.	CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH	3
В.	CONCRETE EXPOSED TO EARTH OR WEATHER: NO.6 THROUGH NO. 18 BAR NO.5 BAR, W31 OR D31 WIRE & SMALLER	2 1 ½"

- 13. MECHANICAL BAR SPLICE CONNECTIONS SHALL CONFORM TO THE REQUIREMENTS OF ACI 318-14 SECTION 25.5.7 USE OF MECHANICAL CONNECTIONS SHALL BE APPROVED BY THE STRUCTURAL ENGINEER. SPLICES MUST BE TESTED AS INDICATED IN THE CONCRETE REINFORCEMENT SPECIFICATION. ACCEPTABLE PRODUCTS
 - LENTON STANDARD COUPLERS (IAPMO-ES 0129)
 - LENTON FORM SAVERS, TYPE SA (IAPMO-ES 0129) LENTON WELDABLE HALF COUPLERS (IAPMO-ES 0129)
 - LENTON LOCK COUPLERS PER (IAPMO-ES 0129)

NOTE THAT REBAR ATTACHED TO PLATE USING LENTON WELDABLE HALF COUPLERS SHALL BE ASTM A706 PER IAPMO-ES 0129.


ALL MECHANICAL BAR SPLICE CONNECTIONS IN SPECIAL STRUCTURAL WALLS, SPECIAL MOMENT FRAMES AND CONCRETE DIAPHRAGMS SHALL BE TYPE 2 CONFORMING TO THE REQUIREMENTS OF ACI 318-14 SECTION 18.2.7 & 18.12.7.4

FOUNDATION

GEOTECHNICAL INFORMATION AND FOUNDATION DESIGN IS BASED ON THE FOLLOWING GEOTECHNICAL REPORTS AND SUPPLEMENTS/ADDENDUMS. COPIES OF THE REPORTS AND SUPPLEMENTAL LETTERS SHALL BE AVAILABLE AT THE JOBSITE AT ALL TIMES.

REPORT/ADDENDUM TITLE	PREPARED BY	DATE	PROJECT #
GEOTECHNICAL INVERSTIGATION FOR GROVE PARK RENOVATIONS	BSK ASSOCIATES	07/20/2021	G21-173-11L
DEDICTION CA			

2. LATERAL EARTH PRESSURES:



3. POLE FOOTINGS:

MIN Ø	Ø ALLOWABLE BEARING CAPACITY (PSF) A BEARING (PSF/FT BELOW GRADE)		SKIN FRICTION RESISTANCI (PSF)	
18"	2,000	250	670	

- A. THE ALLOWABLE CAPACITY MAY BE INCREASED BY ONE-THIRD WHEN CONSIDERING LOADS OF SHORT DURATION SUCH AS WIND OR SEISMIC FORCES.
- B. THE ALLOWABLE LATERAL RESISTANCE CAN BE TAKEN AS THE SUM OF THE FRICTIONAL RESISTANCE AND PASSIVE RESISTANCE WITH THE LESSER REDUCED BY 33 PERCENT.
- C. THE UPPER 1 FOOT OF SOIL NOT PROTECTED BY PAVEMENT SHALL BE NEGLECTED WHEN CALCULATING PASSIVE RESISTANCE.
- D. COMPACTED FILL SHOULD BE PREPARED PER THE GRADING SPECIFICATIONS.
- 4. SLAB ON GRADE SUPPORT SHALL BE PER THE GEOTECHNICAL INVESTIGATION REPORT AND TYPICAL DETAILS IN THE CONSTRUCTION DOCUMENTS.
- WHERE NOT SHOWN ON THE DRAWINGS, CONTRACTOR TO PROVIDE FOR DESIGN AND INSTALLATION OF ALL CRIBBING, SHEATHING AND SHORING REQUIRED AND SHALL BE SOLELY RESPONSIBLE FOR ALL EXCAVATION PROCEDURES INCLUDING LAGGING, SHORING, AND PROTECTION OF ADJACENT PROPERTY, STRUCTURES, STREETS, AND UTILITIES IN ACCORDANCE WITH ALL NATIONAL, STATE AND LOCAL SAFETY ORDINANCES.
- 6. CONTRACTOR TO PROVIDE FOR DE-WATERING OF EXCAVATIONS FROM SURFACE WATER, GROUND WATER AND/OR SEEPAGE.
- EXCAVATION FOR FOOTINGS SHALL BE APPROVED BY THE INSPECTOR OR GEOTECHNICAL ENGINEER PRIOR TO PLACING CONCRETE AND REINFORCING.
- 8. ALL EXCAVATIONS SHALL BE PROPERLY BACKFILLED. DO NOT PLACE BACKFILL BEHIND RETAINING WALLS BEFORE CONCRETE OR GROUT HAS ATTAINED FULL DESIGN STRENGTH. CONTRACTOR SHALL BRACE OR PROTECT ALL BUILDING AND PIT WALLS BELOW GRADE FROM LATERAL LOADS UNTIL ATTACHING FLOORS ARE COMPLETELY IN PLACE AND HAVE ATTAINED FULL DESIGN STRENGTH, CONTRACTOR SHALL PROVIDE FOR DESIGN, PERMITS AND INSTALLATION OF SUCH BRACING.
- 9. FOOTING BACKFILL AND UTILITY TRENCH BACKFILL WITHIN BUILDING AREA SHALL BE MECHANICALLY COMPACTED IN LAYERS IN ACCORDANCE WITH THE GEOTECHNICAL INVESTIGATION REPORT AND APPROVED BY THE GEOTECHNICAL ENGINEER. FLOODING WILL NOT BE PERMITTED. ALL FILLS USED TO SUPPORT FOUNDATIONS SHALL BE INSPECTED BY THE GEOTECHNICAL ENGINEER REPRESENTATIVE PER SECTION 1705.6 OF THE CODE.
- 10. ALL ABANDONED FOOTINGS, UTILITIES, ETC. SHALL BE REMOVED. NEW FOOTINGS MUST EXTEND INTO UNDISTURBED SOILS.

CONCRETE

- ALL CONCRETE CONSTRUCTION SHALL CONFORM WITH CHAPTER 19 OF THE CODE AND WITH THE PROVISIONS OF ACI 318-14.
- 2. CONCRETE MATERIALS SHALL BE IN ACCORDANCE WITH THE FOLLOWING STANDARDS:

MATERIAL	ASTM STANDARD
PORTLAND CEMENT (TYPE II) ^A	C150
CONCRETE AGGREGATES (HARDROCK)	C33
CONCRETE AGGREGATES (LIGHTWEIGHT) ^C	C330
WATER ^B	C1602
COAL FLY ASH OR POZOLLAN (CLASS F)	C618
NATURAL OR MANUFACTURED SAND	C33

- A. FOR SOILS WITH HIGH CONCENTRATIONS OF SULFATES (EXPOSURES S2 OR S3 PER ACI 318-14 TABLE 19.3.2.1) PORTLAND CEMENT SHALL BE TYPE V. VERIFY WITH PROJECT GEOTECHNICAL REPORT.
- B. WATER SHOULD ONLY BE ADDED AT THE BATCH PLANT. IN NO CASE SHALL THE DESIGN WATER/ CEMENT RATIO BE EXCEEDED.
- C. PUMICE AGGREGATE SHALL NOT BE USED.
- 3. CONCRETE MIXES SHALL BE PROPORTIONED BASED ON SECTION 26.4.3 OF ACI 318-14. SCHEDULE OF STRUCTURAL CONCRETE STRENGTHS AND LOCATIONS (UNO):

LOCATION IN STRUCTURE	MINIMUM STRENGTH (PSI)	DENSITY (PCF)	MAX SLUMP (IN±1)	MAX WATER/CEMENT RATIO	FLY ASH BY WT (MAX)
FENCE POST AND SITE WALLS FOUNDATION	3,000	150	4	0.40	0.15

- 4. READY MIXED CONCRETE SHALL BE MIXED AND DELIVERED IN ACCORDANC.E WITH THE REQUIREMENTS OF ASTM C94 OF C685.
- 5. DEPOSITING AND CONVEYING OF CONCRETE SHALL CONFORM TO SECTION 26.5 OF ACI 318-14 AND PROJECT SPECIFICATIONS.
- 6. ALL CONCRETE SURFACES AGAINST WHICH NEW CONCRETE IS TO BE PLACED SHALL BE CLEANED AND ROUGHENED TO 1/4" AMPLITUDE.

7. ALL REINFORCING BARS, ANCHOR BOLTS AND OTHER CONCRETE INSERTS SHALL BE WELL SECURED IN

PROVIDE SLEEVES FOR PLUMBING AND ELECTRICAL OPENINGS IN CONCRETE BEFORE PLACING. DO NOT CUT ANY REINFORCING WHICH MAY CONFLICT. CORING IN CONCRETE IS NOT PERMITTED WITHOUT SEOR APPROVAL. NOTIFY THE SEOR IN ADVANCE OF CONDITIONS NOT SHOWN ON THE DRAWINGS. SEE THE

DRAWINGS FOR ADDITIONAL RESTRICTIONS ON THE PLACEMENT OF OPENINGS IN SLABS AND WALLS.

9. PIPES EMBEDDED IN CONCRETE:

POSITION PRIOR TO PLACING CONCRETE.

- A. CONCRETE a. PIPES LARGER THAN 1-1/2" DIAMETER SHALL NOTE BE EMBEDDED IN STRUCTURAL CONCRETE
 - EXCEPT WHERE SPECIFICALLY APPROVED BY SEOR.). PIPES SHALL NOT DISPLACE OR INTERRUPT REINFORCING BARS.
- C. DO NOT STACK CONDUITS, SPACE EMBEDDED PIPES AND CONDUITS AT A MINIMUM OF 3 DIAMETERS CLEAR FROM OTHER EMBEDDED PIPES/CONDUITS AND REBAR.

GENERAL

- 1. ALL WORK SHALL CONFORM TO THE MINIMUM STANDARDS OF THE FOLLOWING CODES AND STANDARDS:
- A. 2019 CALIFORNIA BUILDING CODE, PART 2, VOLUME 2 OF 2, AND TITLE 24 C.C.R. 2019 EDITION AND LATEST REVISIONS (INCLUDING SUPPLEMENTS AND ERRATA) HEREIN REFERRED TO AS "THE CODE".
- B. ANY OTHER REGULATING AGENCIES WHICH HAVE AUTHORITY OVER ANY PORTION OF THE WORK, INCLUDING THE STATE OF CALIFORNIA DIVISION OF OCCUPATIONAL SAFETY AND HEALTH (CAL/OSHA).
- C. CODES & STANDARDS REFERENCED IN THE CODE OR LISTED IN THESE NOTES AND SPECIFICATIONS.
- ALL DRAWINGS ARE CONSIDERED TO BE A PART OF THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REVIEW AND COORDINATION OF ALL DRAWINGS AND SPECIFICATIONS PRIOR TO THE START OF CONSTRUCTION. ANY DISCREPANCIES THAT OCCUR SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT PRIOR TO START OF CONSTRUCTION SO THAT A CLARIFICATION CAN BE ISSUED. ANY WORK PERFORMED IN CONFLICT WITH THE CONTRACT DOCUMENTS OR ANY CODE REQUIREMENTS SHALL BE CORRECTED BY THE CONTRACTOR AT THEIR OWN EXPENSE AND AT NO EXPENSE TO THE OWNER OR
- NOTES AND DETAILS ON DRAWINGS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS. WHERE NO DETAILS ARE GIVEN, CONSTRUCTION SHALL BE AS SHOWN FOR SIMILAR WORK.
- 4. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO STARTING CONSTRUCTION. THE ARCHITECT SHALL BE NOTIFIED OF ANY DISCREPANCIES OR INCONSISTENCIES. IN NO INSTANCE SHALL DIMENSIONS BE SCALED FROM THE DRAWINGS.
- 5. SEE MECHANICAL, PLUMBING AND ELECTRICAL DRAWINGS FOR THE FOLLOWING:
- A. PIPE RUNS, SLEEVES, HANGERS, TRENCHES, WALL AND SLAB OPENINGS, ETC., EXCEPT AS SHOWN OR NOTED.
- B. ELECTRICAL CONDUIT RUNS, BOXES, OUTLETS IN WALLS AND SLABS.
- C. CONCRETE INSERTS FOR ELECTRICAL, MECHANICAL OR PLUMBING FIXTURES. D. SIZE AND LOCATION OF MACHINE OR EQUIPMENT BASES, ANCHOR BOLTS FOR
- MOTOR MOUNTS.
- 6. SEE CIVIL DRAWINGS FOR THE FOLLOWING HEIGHT AND/OR ELEVATION OF: a. FINISHED SURFACE
 - b. TOP OF WALL
 - c. TOP OF GRADE d. FINISHED GRADE
- e. SLOPE F. SITE CONCRETE WALKWAYS, CURBS & PAVING
- THE CONTRACT STRUCTURAL DRAWINGS AND SPECIFICATIONS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE METHOD OF CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY TO PROTECT THE STRUCTURE DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO, BRACING, SHORING FOR LOADS DUE TO CONSTRUCTION EQUIPMENT ETC. THE CONTRACTOR IS RESPONSIBLE FOR PROVISION OF TEMPORARY SHORING AND OTHER CONSTRUCTION AIDS, INCLUDING ALL ENGINEERING OF SUCH SYSTEMS, FOR TEMPORARY SUPPORT OF NEW AND/OR EXISTING STRUCTURAL ELEMENTS AS REQUIRED FOR ERECTION AND OTHER CONTRACTOR'S MEANS AND METHODS OF CONSTRUCTION (UNO). OBSERVATION VISITS TO THE SITE BY THE STRUCTURAL ENGINEER SHALL NOT INCLUDE INSPECTION OF THE ABOVE ITEMS OR CONCERN CONSTRUCTION MEANS AND METHODS OR CONSTRUCTION
- BACKFILL SHALL NOT BE PLACED BEHIND EXTERIOR AND INTERIOR RETAINING WALLS UNTIL THE CONCRETE / CMU HAS ACHIEVED FULL DESIGN STRENGTH. FOR BRACED WALLS SUPPORTED BY STRUCTURAL DIAPHRAGMS. BACKFILL SHALL NOT BE PLACED BEHIND THE WALL UNTIL THE DIAPHRAGM HAS BEEN INSTALLED, AND FOR CONCRETE DIAPHRAGMS, HAS ACHIEVED FULL DESIGN STRENGTH.
- THE CONTRACT STRUCTURAL DRAWINGS SHOW THE BUILDING IN ITS FINAL INTENDED POSITION, CONTRACTOR SHALL MAKE PROVISIONS IN THE LAYOUT OF THE BUILDING TO TAKE INTO ACCOUNTS SHRINKAGE, CREEP, SHORTENING, ETC..
- 10. OPENINGS, POCKETS, ETC., LARGER THAN 6" SHALL NOT BE PLACED IN CONCRETE SLABS, DECKS, WALLS, DRAWINGS BY OTHERS SHOW OPENINGS, POCKETS, ETC., LARGER THAN 6" NOT SHOWN ON THE STRUCTURAL DRAWINGS, BUT WHICH ARE LOCATED IN STRUCTURAL MEMBERS.
- 11. ASTM SPECIFICATIONS ON THE DRAWINGS SHALL BE THE VERSION REFERENCED IN CHAPTER 35 OF THE CODE OR AS REFERENCED IN THE APPLICABLE DESIGN STANDARD.
- 12. CONTRACTOR SHALL INVESTIGATE SITE DURING CLEARING AND EARTHWORK OPERATIONS FOR FILLED EXCAVATIONS OR BURIED STRUCTURES, SUCH AS CESSPOOLS, CISTERNS, FOUNDATIONS, ETC. IF ANY SUCH STRUCTURES ARE FOUND, THE STRUCTURAL ENGINEER AND GEOTECHNICAL ENGINEER SHALL BE NOTIFIED
- 13. CONSTRUCTION MATERIAL SHALL BE SPREAD OUT IF PLACED ON FRAMED ROOF OR FLOOR. LOAD SHALL NOT EXCEED THE DESIGN LIVE LOAD PER SQUARE FOOT. THE CONTRACTOR TO DESIGN AND PROVIDE ADEQUATE SHORING AND/OR BRACING WHERE STRUCTURE HAS NOT ATTAINED DESIGN STRENGTH.
- 14. CONTRACTOR SHALL COORDINATE SHORING WITH DRAWINGS OF RECORD TO INSURE PROVISIONS FOR POCKETS, BLOCKOUTS, OFFSETS, STEPPED FOOTINGS AND ANY OTHER ITEMS AFFECTED BY THE SHORING
- 15. AN UNDERGROUND SERVICE ALERT INQUIRY IDENTIFICATION NUMBER MUST BE OBTAINED AT LEAST TWO
- WORKING DAYS BEFORE STARTING WORK WITH THIS PERMIT. A. FOR PROJECTS IN SOUTHERN CALIFORNIA - TELEPHONE NO. : 1-800-422-4133 B. FOR PROJECTS IN NORTHERN CALIFORNIA - TELEPHONE NO. : 1-800-227-2600


DESIGN INFORMATION


1. WIND DESIGN DATA (2019 CBC SECTION 1603.1.4):

WIND DESIGN DATA					
PARAMETER	VALUE	REFERENCE			
ULTIMATE DESIGN WIND SPEED (3-SEC GUST)	V _{ULT} = 92 MPH	2019 CBC FIG. 1609.3			
NOMINAL DESIGN WIND SPEED (3-SEC GUST)	V _{ASD} = 72 MPH	2019 CBC 1609.3.1			
EXPOSURE CATEGORY	С	2019 CBC 1609.4.3			
INTERNAL PRESSURE COEFFICIENT:	GCpi = ± 0.18	ASCE 7-16 TABLE 26.13-1			

EARTHQUAKE DESIGN DATA (2019 CBC SECTION 1603	.1.5):	
SITE AND OCCUP	ANCY PARAMETERS	
PARAMETER	VALUE	REFERENCE
RISK CATEGORY	II	2019 CBC TABLE 1604.5
SEISMIC IMPORTANCE FACTOR	I = 1.0	ASCE 7-16 TABLE 1.5-2
MAPPED SPECTRAL RESPONSE ACCELERATIONS:	S s = 2.093	2019 CBC 1613.2.1
MAPPED SPECIKAL RESPONSE ACCELERATIONS.	S ₁ = 0.805	Z019 CBC 1613.2.1
SITE CLASS	D (DEFAULT)	2019 CBC 1613.2.2
SPECTRAL RESPONSE COEFFICIENTS:	S DS = 1.674	2019 CBC 1613.2.4
ISPECTRAL RESPONSE COEFFICIENTS:	S D1 = 0.912	ZU17 CDC 1013.2.4


3. GEOTECHNICAL INFORMATION (2019 CBC SECTION 1603.1.6): REFER TO FOUNDATION GENERAL NOTES





POST PIER FOOTING 1/2" = 1'-0"





△ ≥ SVE PARI ROUND | Ther King Jr.

S

 $\ll =$

 $Q \overline{Q}$

NO. REVISION DATE COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218 PROJECT MANAGER C. CECIL

CHECKED BY

J. LONG C. CECIL NOVEMBER 22, 2022 PROJECT NUMBER

2211-01-RC21 SHEET

DRAWN BY

BID

IRRIGATION SCHEDULE

SYMBOL	MANUFACTURER/MODEL/DESCRIPTION	<u>PSI</u>	<u>GPM</u>	<u>RADIUS</u>	<u>DETAIL</u>
10	HUNTER I-25-06-SS TURF ROTOR, 6" POP-UP. ADJUSTABLE AND FULL CIRCLE. STAINLESS STEEL RISER. DRAIN CHECK VALVE. STANDARD NOZZLE.	50	10.1	51'	5/LI501
15	HUNTER I-25-06-SS TURF ROTOR, 6" POP-UP. ADJUSTABLE AND FULL CIRCLE. STAINLESS STEEL RISER. DRAIN CHECK VALVE. STANDARD NOZZLE.	50	13.4	56'	5/LI501
SYMBOL	MANUFACTURER/MODEL/DESCRIPTION				<u>DETAIL</u>
•	RAIN BIRD EFB-CP 1", 1-1/2", 2" BRASS REMOTE CONTROL VALVE, THAT IS CONTAMINATION PROOF W/SELF-FLUSHING FILTER SCREEN. GLOBE CONFIGURATION, RECLAIMED WATER COMPATIBLE, AND PURPLE HANDLE COVER DESIGNATES NON-POTABLE WATER USE.				4/LI501
	IRRIGATION LATERAL LINE: PVC SCHEDULE 40				
	IRRIGATION MAINLINE: PVC SCHEDULE 40				


(EXISTING)

VALVE SCHEDULE

Valve Callout

NUMBER	MODEL	SIZE	<u>TYPE</u>	<u>GPM</u>	<u>PSI</u>	<u>PRECIP</u>
1	RAIN BIRD EFB-CP	2"	TURF ROTOR	40.2	54.63	1.93 in/h
2	RAIN BIRD EFB-CP	2"	TURF ROTOR	40.4	56.05	0.77 in/h
3	RAIN BIRD EFB-CP	2"	TURF ROTOR	53.6	53.38	0.46 in/h
4	RAIN BIRD EFB-CP	2"	TURF ROTOR	40.4	53.96	0.87 in/h
5	RAIN BIRD EFB-CP	2"	TURF ROTOR	40.4	54.33	0.43 in/h
6	RAIN BIRD EFB-CP	2"	TURF ROTOR	50.5	54.69	1.49 in/h
7	RAIN BIRD EFB-CP	2"	TURF ROTOR	40.4	54.23	0.73 in/h
8	RAIN BIRD EFB-CP	2"	TURF ROTOR	40.2	53.74	0.45 in/h

WATER USE CALCULATION




IRRIGATION NOTES

- 1. IRRIGATION PLAN IS DIAGRAMMATIC. CONTRACTOR SHALL DETERMINE FINAL LOCATION OF PIPING AT THE TIME OF INSTALLATION. MAINLINE AND LATERALS SHALL BE PLACED IN THE SAME TRENCH WHEN POSSIBLE.
- 2. ALL EQUIPMENT REQUIRED BUT NOT SPECIFIED ON THE DRAWING TO COMPLETE THE WORK SHALL BE PROVIDED BY THE IRRIGATION CONTRACTOR.
- 3. INSTALL ALL EQUIPMENT IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS AND SPECIFICATIONS.
- 4. WORK SHALL BE DONE IN ACCORDANCE WITH THIS SET OF CONSTRUCTION DOCUMENTS.
- 5. CONTRACTOR SHALL BECOME THOROUGHLY FAMILIAR WITH THE PLANS AND SITE CONDITIONS PRIOR TO BEGINNING WORK. SHOULD CONFLICTING INFORMATION BE FOUND ON THE PLANS, THE CONTRACTOR SHALL NOTIFY THE PROJECT LANDSCAPE ARCHITECT BEFORE PROCEEDING WITH THE WORK IN QUESTION.
- 6. DO NOT WILLFULLY INSTALL THE IRRIGATION SYSTEM AS SHOWN ON THE DRAWINGS WHEN IT IS OBVIOUS IN THE FIELD THAT OBSTRUCTIONS, GRADE DIFFERENCES OR DIFFERENCES IN THE AREA DIMENSIONS EXIST THAT MIGHT NOT HAVE BEEN CONSIDERED IN THE ENGINEERING. SUCH OBSTRUCTIONS OR DIFFERENCES SHOULD BE BROUGHT TO THE ATTENTION OF THE CITY OF BERKELEY. IN THE EVENT THIS NOTIFICATION IS NOT PERFORMED, THE CONTRACTOR SHALL ASSUME FULL RESPONSIBILITY FOR ANY REVISIONS NECESSARY AT NO EXPENSE TO THE CITY OF BERKELEY.
- 7. ALL EXISTING UTILITIES, WATER LINES AND FIRE HYDRANTS SHALL REMAIN CONNECTED AND IN FULL CONTINUOUS OPERATION DURING AND FOLLOWING ALL CONTRACT, LANDSCAPE, AND IRRIGATION WORK.
- 8. CONTRACTOR SHALL MAKE ALL NECESSARY ADJUSTMENTS TO THE IRRIGATION SYSTEM FOLLOWING A PRECIPITATION TEST PER THE CITY OF BERKELEY. ADJUSTMENTS SHALL INCLUDE BUT WILL NOT BE LIMITED TO: HEAD RELOCATION, CHANGING NOZZLES, AND ADJUSTING ARC PATTERNS TO ATTAIN EFFICIENT UNIFORMITY AS REQUIRED BY THE CITY OF BERKELEY.
- 9. CONTRACTOR SHALL NOT INSTALL ANY PLANTING UNTIL THE FOLLOWING ARE COMPLETED:
- THE IRRIGATION SYSTEM IS FULLY OPERATIONAL.
- HYDROSTATIC PRESSURE TESTS HAVE BEEN PERFORMED ON MAIN AND LATERAL LINES.
 ALL ZONES HAVE PASSED A COVERAGE TEST.
- CONTROLLERS ARE FULLY OPERATIONAL.
- 10. EXISTING IRRIGATION SYSTEM OUTSIDE THE PROJECT LIMITS SHALL REMAIN OPERATIONAL DURING CONSTRUCTION.




rrmdesign.com | (510) 751-4910 325 Davis St. San Leandro, CA 94577



THE INCLUDED DRAWINGS, SPECIFICATIONS, IDEAS, DESIGNS AND ARRANGEMENTS REPRESENTED THEREBY ARE AND SHALL REMAIN THE PROPERTY OF RRM DESIGN GROUP AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN CONNECTION WITH ANY WORK OR PROJECT TOHER THAN THE SPECIFIED PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND DEVELOPED WITHOUT THE WRITTEN CONSENT OF RRM DESIGN GROUP. VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS, SUBMITTAL OF THESE DOCUMENTS FOR PUBLIC AGENCY REVIEW SHALL NOT BE CONSIDERED A WAIVER OF RRM DESIGN GROUP'S RIGHTS.

RRM DESIGN GROUP COPYRIGHT 2022.

RRM IS A CALIFORNIA CORPORATION




TONS 7, CA 94703

GROUND RENOVATION Luther King Jr. Way, Berkeley, IRRIGATION PLAN


PLAYGROU

NO.	REVISION		DATE
\triangle			
\triangle			
CIT	OB SPECIFICATION Y PLAN NO. 825		
PROJ JS	ECT MANAGER		
	WN BY	CHECKED B	Υ
ΥI		JS	
DATE			
	VEMBER 22, 2	2000	




- 1. SEE SHEET LI001 FOR IRRIGATION NOTES,
- EQUIPMENT SCHEDULE, AND VALVE SCHEDULE. 2. BOXES/VALVE LOCATIONS TO BE MARKED UP AND LOCATED IN FIELD BY CITY OF BERKELEY MAINTENANCE STAFF.
- 3. ALL NUMBERED VALVES ON PLAN ARE
- 4. ALL MAINLINE SHOWN ON PLAN ARE EXISTING.





RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION




IRRIGATION

NO. REVISION


COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218

CHECKED BY

NOVEMBER 22, 2022 PROJECT NUMBER



RRM-2211.01-03



- 24" CLEAR TO ALL HARDSCAPE, TYPICAL.

- PLACE ALL HEADS 1/4" ABOVE FINISH

GRADE AT INITIAL INSTALLATION. SET

- COMPACT SOIL @ EA. HEAD TO 90% REL.

SWING JOINT ASSEMBLY, INCL. (2) SCH

80 STREET ELL, (1) SCH. NIPPLE, SCH. 40

RRM-2211.01-11

RRM-2211.01-30

ELL OR TEE CONNECTIONS AS REQ'D.

CURBS OR MOW STRIPS.

COMP. PER N.T.C.

—— PVC LATERAL LINE

PLAN VIEW

LENGTH AS REQUIRED

MODERATELY SNUG, DO NOT OVERTIGHTEN THREADS.

2. SIZE THE SWING JOINT USING THE FOLLOWING CRITERIA:

REMOTE CONTROL VALVE

• USE A 3/4" SIZE FOR A ROTOR WITH FLOWS LESS THAN 8 GPM. • USE A 1" SIZE FOR A ROTOR WITH FLOWS BETWEEN 8 - 11 GPM.

• USE A 1 1/2" SIZE FOR A ROTOR WITH FLOWS GREATER THAN 11 GPM.

1. ALL PIPE THREADS ON SWING JOINT SHALL BE COATED WITH RECTORSEAL T PLUS

2 TEFLON PIPE COMPOUND OR APPROVED EQUAL BEFORE ASSEMBLY. DO NOT USE


PIPE COMPOUND AND TAPE ON SWING JOINT THREADS. TIGHTEN THREADS UNTIL

PVC SxSxT TEE FITTING

ELEVATION VIEW |

<u>NOTES:</u>

POP-UP ROTOR




C. ALL VALVE BOXES SHALL BE SET 2" ABOVE FINISH GRADE.

\ VALVE BOX LAYOUT IN PLANTERS

D. SEE IRRIGATION PLAN FOR MAINLINE PIPE SIZING.


3/8" = 1'-0"




WIRING CONNECTIONS

RRM-2211.01-06

rrmdesign.com | (510) 751-4910 325 Davis St. San Leandro, CA 94577



RRM DESIGN GROUP COPYRIGHT 2022. RRM IS A CALIFORNIA CORPORATION




ATÍ Berkeley, Ž W IRRIG.

4

DATE NO. REVISION COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218 **PROJECT MANAGER** DRAWN BY CHECKED BY NOVEMBER 22, 2022 PROJECT NUMBER 2211-01-RC21

SHEET








THE INCLUDED DRAWINGS, SPECIFICATIONS, IDEAS, DESIGNS AND ARRANGEMENTS REPRESENTED THEREBY ARE AND SHALL REMAIN THE PROPERTY OF RRM DESIGN GROUP AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN CONNECTION WITH ANY WORK OR PROJECT THER THAN THE SPECIFIED PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND DEVELOPED WITHOUT THE WRITTEN CONSENT OF RRM DESIGN GROUP. WISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS. SUBMITTAL OF THESE DOCUMENTS FOR PUBLIC AGENCY REVIEW SHALL NOT BE CONSIDERED A WAIVER OF RRM DESIGN GROUP'S RIGHTS.

RRM DESIGN GROUP COPYRIGHT 2022.

RRM IS A CALIFORNIA CORPORATION



TIONS By, CA 94703

NE PARK FIELD AN ROUND RENOVATION There King Jr. Way, Berkeley, Old ANTING PLAN


PLAYGROUI 2828 Martin Luther Ki

NO.	REVISION		DATE
\triangle			
\triangle			
\triangle			
\triangle			
\triangle			
	B SPECIFICAT Y PLAN NO. 8		
PROJ	ECT MANAGE	R	
JS			
DRAV	VN BY	CHECKE	O BY
YI		JS	
DATE			

PROJECT NUMBER 22, 2022

2211-01-RC21

LP101



CONDUIT

COPPER

DIAMETER

DRAWING

ELECTRICAL

– ENCLOSURE

GALVANIZED

HANDHOLE

KILOVOLT

KILOWATT

LTG – LIGHTING

KILOVOLT—AMPERE

LIGHT—EMITTING DIODE

EQUAL

EQUIP - EQUIPMENT

CT

ENCL

CIRCUIT BREAKER

COLD WATER PIPE

EXISTING TO REMAIN

- ELECTRICAL METALLIC TUBING

GROUND FAULT CIRCUIT

KILOAMPERES INTERRUPTING

INTERRUPTER

GROUNDING ELECTRODE CONDUCTOR

CURRENT TRANSFORMER

CONDUIT ONLY

NOT IN CONTRACT

NEUTRAL LINK

PHOTOELECTRIC

- POLYVINYL CHLORIDE

RIGID STEEL CONDUIT

RELOCATED EXISTING

EXISTING TO BE REMOVED

- SEE LANDSCAPE DRAWINGS

- TRANSIENT VOLTAGE SURGE SUPPRESSOR

ON CENTER

OVERHEAD

PULLBOX PHOTOCELI

POWER

QUANTITY

SHT - SHEET

SW - SWITCH

VOLT

WATT

WP - WEATHERPROOF

XFMR - TRANSFORMER

RECEPTACLE


SWITCHBOARD

UNDERGROUND

TYPICAL

TO BE DETERMINED

UON - UNLESS OTHERWISE NOTED



(N) MUSCO CONTROL CABINET

LOCATED ON WALL IN CLUBHOUSE

(3) CONTROL DIAGRAM

LIGHTING CONTACTOR, UTILIZING MUSCO CONTROL-LINK CONTROL CABINET AND WIRELESS CONTROL BY REUSING THE EXISTING BALLFIELD ELECTRICAL SWITCHBOARD AND THE



design

rrmdesign.com | (510) 751-4910

325 Davis St. San Leandro, CA 94577


1480 MORAGA ROAD, SUITE C #229

MORAGA, CA 94556

Lic. No. 19459 Exp: 06/30/2023

NO. REVISION COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218 **PROJECT MANAGER** DRAWN BY CHECKED BY **NOVEMBER 22, 2022** PROJECT NUMBER 2211-01-RC21 E-1.1


4866 9/8/22











SROUND RENOVATION Luther King Jr. Way, Berkeley, CA 9 ECTRICAL SITE PLAN

NO. REVISION DATE

COB SPECIFICATION NO. 22-11538-C
CITY PLAN NO. 8256 FILE NO. 406-218

CITY PLAN NO. 8256 FILE NO. 406-2

PROJECT MANAGER

DRAWN BY

CHECKED BY

DRAWN BY CHECKED I
MP RZ


DATE

NOVEMBER 22, 2022


PROJECT NUMBER
2211-01-RC21

E-2.1

4866 9/8/22




MATCHLINE 'A' SEE SHEET E2.1






rrmdesign.com | (510) 751-4910 325 Davis St. San Leandro, CA 94577







GROVE PARK FIELD AND
LAYGROUND RENOVATIONS
Martin Luther King Jr. Way, Berkeley, CA 947 ELECTRICAL

COB SPECIFICATION NO. 22-11538-C CITY PLAN NO. 8256 FILE NO. 406-218 PROJECT MANAGER

CHECKED BY

NOVEMBER 22, 2022 PROJECT NUMBER

2211-01-RC21

E-2.2

4866 9/8/22