



Department of Parks, Recreation and Waterfront
Waterfront Capital Improvements Program Division

September 19, 2025

**CITY OF BERKELEY
TOM BATES REGIONAL SPORTS COMPLEX
COMMUNITY FACILITY, PICKLEBALL COURTS AND U8 SOCCER FIELD
SPEC. NO. 25-11736-C**

ADDENDUM NO. 3

Dear Bidder:

The following amendments are hereby made to the subject documents:

1. **Specifications:** Section 00 4113 Bid Form
REPLACE with attached revised Section 00 4113 Bid Form
Changes were made to add bid items A2.03A, B1.05A, C3.04A, BA1.06A, and BA2.04A -
“Disposal of Surplus Material to General Landfill”.
2. **Specifications:** Section 31 2000 Earth Moving, Part 4 - Measurement and Payment
REPLACE with attached revised Section 31 2000 Earth Moving, Part 4 – Measurement and Payment (page 31 20000-8).

In addition, the following clarifications are hereby made to the subject documents:

Questions and Responses:

1. Please confirm whether the parking lot is to be stripe using thermoplastic or paint.

Response: Parking lot striping shall be paint.

In accordance with this Addendum No.3, the Bid Opening has been postponed to **2:00 p.m., Tuesday, September 30, 2025.**

TBRSC – Community Facility, Pickleball Courts and U8 Soccer Field
Specification No. 25-11736-C
Addendum No. 3
September 19, 2025

All other provisions of the contract documents shall remain the same. **Bidders shall submit a signed acknowledgment of Addendum No. 3 along with their Bidder's Proposal. Failure to do so may result in bid rejection.**

Sincerely,



Jesus Espinoza
Associate Civil Engineer

BIDDER'S ACKNOWLEDGEMENT:

TOM BATES REGIONAL SPORTS COMPLEX – COMMUNITY FACILITY, PICKLEBALL COURTS AND U8 SOCCER FIELD, SPEC. NO. 25-11736-C

Name of Company: _____

Address, City, State, Zip: _____

Signature: _____

Title: _____

Print Name: _____

Date: _____

Tom Bates Regional Sports Complex
Community Facility, Pickleball Courts and U8 Soccer Field

Specification No. 25-11736-C

DOCUMENT 00 4113
BID FORM

TO CITY OF BERKELEY

THIS BID IS SUBMITTED BY:

(Firm/Company Name)

Re: Tom Bates Regional Sports Complex, Community Facility, Pickleball Courts and U8 Soccer Field, at 400-408 Gilman Street, Berkeley, CA 94710, Specification No. 25-11736-C.

1. The undersigned Bidder proposes and agrees, if this Bid is accepted, to enter into an agreement with City of Berkeley in the form included in the Contract Documents, Document 00 5200 (Agreement), to perform and furnish all Work as specified or indicated in the Contract Documents for the Contract Sum and within the Contract Time indicated in this Bid and in accordance with all other terms and conditions of the Contract Documents.
2. Bidder accepts all of the terms and conditions of the Contract Documents, Document 00 1113 (Notice Inviting Bids), and Document 00 2113 (Instructions to Bidders), including, without limitation, those dealing with the disposition of Bid Security. This Bid will remain subject to acceptance for 60 calendar days after the day of Bid opening, unless there is a bid protest, then 90 calendar days after the day of bid opening. Bidder will sign and submit Document 00 5200 (Agreement) and other documents required by Document 002113, paragraph 5.02 (Required Contract Documents and Proof of Insurance) within 20 calendar days after receipt of City's Notice of Intent to Award.
3. In submitting this Bid, Bidder represents that Bidder has examined all of the Contract Documents, performed all necessary Pre-Bid investigations as set forth in Document 00 5200 (Agreement) Article 6 (Contractor's Representation), received the Pre-Bid conference minutes (if any), and received the following Addenda:

Addendum Number	ADDENDUM DATE	Signature of Bidder

4. Based on the foregoing, Bidder proposes and agrees to fully perform the Work within the time stated and in strict accordance with the Contract Documents for the following sums of money listed in the following Schedule of Bid Prices:

SCHEDULE OF BID PRICES

All Bid items, including lump sums and unit prices, must be filled in completely. All Bids include all labor, materials, services, and equipment necessary for the completion of all Work shown on the plans, specifications, and other Contract Documents, including connections to existing systems, to provide a complete and finished project. Each Bid item shall include all work as described, except for work separately requested under other Bid Items. Bid items are described in Section 01 1100 (Summary of Work). Quote in figures only, unless words are specifically requested.

Base Bid

Schedule A – Prefabricated Building, Associated Access and Utility Improvements

ITEM	DESCRIPTION	Quantity	Unit	Unit Price	Item Total
Site Preparation and Demolition					
A1.01	Mobilization	1	LS		
A1.02	Prepare and Implement SWPPP	1	LS		
A1.03	Traffic Control System	1	LS		
A1.04	Temporary Fence	1,171	LF		
A1.05	Temporary Parking	1	LS		
A1.06	Construction Staking	1	LS		
A1.07	Remove Asphalt Concrete Pavement	645	SY		
A1.08	Remove Chain Link Fence	128	LF		
A1.09	Remove 3" Water Service Pipe	116	LF		
A1.10	Remove Striping and Pavement Markings	1	LS		
A1.11	Remove Wheel Stop	14	EA		
A1.12	Remove Sign	2	EA		
A1.13	Relocate Utility Box	1	EA		
Grading and Drainage					
A2.01	Cut and Fill	211	CY		
A2.02	Fine Grading (Landscape areas only)	540	SF		
A2.03	Dispose Contaminated Soil (Class 2)	183	CY		
A2.03A	Off-haul Soil Suitable for General Landfill	20	CY		
A2.04	Dewatering	1	LS		
A2.05	6" HDPE Perforated Pipe	10	LF		

A2.06	6" HDPE Roof Leader	37	LF		
A2.07	8" HDPE Storm Drain Pipe	23	LF		
A2.08	Storm Drain Manhole	1	EA		
A2.09	Storm Drain Inlet	1	EA		
A2.10	Storm Drain Cleanout	1	EA		
A2.11	Energy Dissipator	3	EA		
Utilities					
A3.01	2" HDPE Water Pipe	62	LF		
A3.02	3" HDPE Water Pipe	147	LF		
A3.03	6" HDPE Fire Hydrant Lateral	131	LF		
A3.04	8" HDPE Water Main	217	LF		
A3.05	Water Valve and Box	1	EA		
A3.06	6" Gate Valve	1	EA		
A3.07	8" Gate Valve	1	EA		
A3.08	Blowoff Valve	1	EA		
A3.09	Fire Hydrant	1	EA		
A3.10	6" HDPE Sanitary Sewer Force Main	314	LF		
A3.11	6" HDPE Sanitary Sewer	109	LF		
A3.12	Sanitary Sewer Cleanout	4	EA		
A3.13	Engineered Wastewater Pump Station	1	LS		
A3.14	Electric Service (Utility)	1	LS		
A3.15	112.5 kVA Pad-mounted Dry Type Transformer	1	LS		
A3.16	400A Panel (Panel-A)	1	EA		
A3.17	Lighting Control Panel	1	EA		
A3.18	Level 2 Dual EVCS (Incl. OCP device, 2 bollards, trenching, circuit, conduit, & 1 pull box)	1	EA		
A3.19	EVCS Ready (Incl. trenching, conduits, and (2) pullbox for (2) future EVCS)	2	EA		
A3.20	Pole Top Light Fixture	1	EA		

A3.21	3" PVC Conduit with Pull String	15	LF		
A3.22	250A Feeder 3" PVC conduit, (3) # 250KCMIL, #2 GND (To Panel-A)	20	LF		
A3.23	125A Feeder 1-1/2" PVC conduit, (3) #1 AWG, #4 GND (To Panel B)	50	LF		
A3.24	100A Feeder 2" PVC conduit, 2-sets of (4) 3/0 AWG, #4 GND	1,150	LF		
A3.25	Lift Station circuit 2" PVC Conduit in Trench, (3) #1 Awg (1) #6 Awg	200	LF		
A3.26	Lighting Circuit 1-1/4" PVC Conduit, (3) #10 Awg.	100	LF		
A3.27	Utility Pull Box	8	EA		
A3.28	Trench	700	LF		
A3.29	Telecomm. Service	1	LS		
A3.30	Telecomm. Service Panel	1	EA		
Building					
A4.01	Retaining Wall Piles	36	EA		
A4.02	Building Retaining Wall	130	LF		
A4.03	Building and Open Plaza Piles	49	EA		
A4.04	Structural Slab for Building and Open Plaza	3,165	SF		
A4.05	Prefabricated Restroom/Storage Building	1	LS		
A4.06	Furnishing and Equipment (Chairs, Whiteboard, etc.) – Allowance	1	LS	\$10,000	
A4.07	Roof Drainage System	1	LS		
Site Improvements					
A5.01	PCC Topping Slab (Including Sand Base)	1,737	SF		
A5.02	Stamped Concrete Pattern	1,468	SF		
A5.03	6' Chain Link Fence	28	LF		
A5.04	5' Wide Chain Link Gate	2	EA		
A5.05	Guardrail for Retaining Wall	23	LF		
A5.06	PCC Stairs (Including AB)	100	LF Nose		
A5.07	Handrail for Stairs	48	LF		
A5.08	Retaining Wall for ADA Ramp	185	LF		
A5.09	Handrail for ADA Ramp	129	LF		

A5.10	Guardrail for ADA Ramp	56	LF		
A5.11	PCC Walkway/Ramp Pavement (Including AB)	1,505	SF		
A5.12	Concrete Curb Ramp (Including AB)	2	EA		
A5.13	Detectable Warning Surfacing	26	SF		
A5.14	6" Vertical Curb	341	LF		
A5.15	Aggregate Base (Under HMA)	59	CY		
A5.16	Hot Mix Asphalt (Type A)	37	TON		
A5.17	Wheel Stop	15	EA		
A5.18	Signing and Striping	1	LS		
A5.19	Opening in Existing Chain Link Fence	25	LF		
A5.20	Concrete Bioswale Structure	8	CY		
A5.21	Permeable Material	3	CY		
A5.22	Bioretention Soil	4	CY		
Landscaping and Site Furnishings					
A6.01	Irrigation Controller	1	EA		
A6.02	Irrigation Drip System	540	SF		
A6.03	Compost Soil Amendment	4	CY		
A6.04	Mulch (3" Thick)	5	CY		
A6.05	Sheet Mulch Cardboard (2 Layers, Recycled)	540	SF		
A6.06	Shrubs (1 Gallon)	35	EA		
A6.07	Shrubs (5 Gallon)	11	EA		
A6.08	Bench	1	EA		
A6.09	Bench Half Round	4	EA		
A6.10	Picnic Table, ADA Compliant	2	EA		
A6.11	Trash and Recycling Receptacle (single)	2	EA		
A6.12	Shade Sail/Awning	1	LS		
A6.13	Landscape Establishment (180 days)	540	SF		
Total Base Bid Schedule A Price: (Bid Items A1.01 through A6.13)					

Schedule B – Asphalt Pickleball Courts First Half and Bioretention Basin

ITEM	DESCRIPTION	Quantity	Unit	Unit Price	Item Total
Asphalt Pickleball Courts First Half					
B1.01	Mobilization	1	LS		
B1.02	Implement SWPPP	1	LS		
B1.03	Construction Staking	1	LS		
B1.04	Clearing and Grubbing	0.33	AC		
B1.05	Cut and Fill	730	CY		
B1.05A	Off-haul Soil Suitable for General Landfill	770	CY		
B1.06	Fine Grading (Landscape areas only)	4,768	SF		
B1.07	8" HDPE Storm Drain Pipe	93	LF		
B1.08	8" HDPE Perforated Pipe	196	LF		
B1.09	12" HDPE Storm Drain Pipe	23	LF		
B1.10	Trench Drain	97	LF		
B1.11	Storm Drain Manhole	2	EA		
B1.12	Storm Drain Inlet	1	EA		
B1.13	Storm Drain Cleanout	2	EA		
B1.14	Basin Outlet	2	EA		
B1.15	Permeable Material	63	CY		
B1.16	Bioretention Soil	95	CY		
B1.17	PCC Walkway/Ramp Pavement (Including AB)	1,672	SF		
B1.18	Aggregate Base (Under HMA and for Bioretention Access Road)	213	CY		
B1.19	Hot Mix Asphalt (Type A)	2	TON		
B1.20	6' Chain Link Fence	75	LF		
B1.21	6' Wide Chain Link Gate	2	EA		
B1.22	Opening in Existing Chain Link Fence	16	LF		
B1.23	18" Wide Concrete Header	158	LF		

Addendum 3

Tom Bates Regional Sports Complex
Community Facility, Pickleball Courts and U8 Soccer Field

Specification No. 25-11736-C

B1.24	Asphalt Concrete Pavement for Pickleball Court	114	TON		
B1.25	Color Surfacing System	5,949	SF		
B1.26	10' High Chain Link Fence	256	LF		
B1.27	3' Wide Chain Link Gate	2	EA		
B1.28	Wind Screening Material for Pickleball Court	2,300	SF		
B1.29	Net System and Posts	3	EA		
B1.30	Irrigation Drip System	4,366	SF		
B1.31	Compost Soil Amendment	27	CY		
B1.32	Mulch (3" Thick)	40	CY		
B1.33	Sheet Mulch Cardboard (2 Layers, Recycled)	4,366	SF		
B1.34	Biofiltration Sod	1,894	SF		
B1.35	Shrubs (1 Gallon)	294	EA		
B1.36	Shrubs (5 Gallon)	40	EA		
B1.37	Bench	4	EA		
B1.38	Landscape Establishment (180 days)	4,366	SF		
Total Base Bid Schedule B Price (Bid Items B1.01 through B1.38)					

Schedule C – U8 Soccer Field

ITEM	DESCRIPTION	Quantity	Unit	Unit Price	Item Total
U8 Soccer Field					
C3.01	Mobilization	1	LS		
C3.02	Construction Staking	1	LS		
C3.03	Clearing and Grubbing	0.41	AC		
C3.04	Cut and Fill	912	CY		
C3.04A	Off-haul Soil Suitable for General Landfill	750	CY		
C3.05	Fine Grading (Landscape areas only)	15,100	SF		
C3.06	8" HDPE Storm Drain Pipe	117	LF		
C3.07	Aggregate Base (Under HMA)	14	CY		

C3.08	Hot Mix Asphalt (Type A)	8	TON		
C3.09	24" Wide Concrete Header	501	LF		
C3.10	Irrigation Spray System	15,079	SF		
C3.11	Compost Soil Amendment	92	CY		
C3.12	Sod Lawn	15,079	SF		
C3.13	20' High Chain Link and Netting Fence	373	LF		
C3.14	6' Wide Chain Link Gate	3	EA		
C3.15	Wind Screening Material for Soccer Field	3,730	SF		
C3.16	Soccer Field Marking	1	LS		
C3.17	Soccer Goal	2	EA		
C3.18	Landscape Establishment (180 days)	15,079	SF		
Total Base Bid Schedule C Price (Bid Items C3.01 through C3.18)					

DESCRIPTION	PRICE (\$)
Schedule A – Prefabricated Building, Associated Access and Utility Improvements	
Schedule B – Asphalt Pickleball Courts First Half and Bioretention Basin	
Schedule C – U8 Soccer Field	
Total Base Bid Price - Schedules A, B and C	

Total Base Bid Price: (Schedules A, B and C)

(Words)

Bid Alternates**Bid Alternate 1 - Asphalt Pickleball Courts 2nd Half**

ITEM	DESCRIPTION	Quantity	Unit	Unit Price	Item Total
Bid Alternate 1 - Asphalt Pickleball Courts Second Half					
BA1.01	Mobilization	1	LS		
BA1.02	Implement SWPPP	1	LS		
BA1.03	Construction Staking	1	LS		
BA1.04	Clearing and Grubbing	0.26	AC		
BA1.05	Remove Chain Link Fence	128	LF		
BA1.06	Cut and Fill	587	CY		
BA1.06A	Off-haul Soil Suitable for General Landfill	380	CY		
BA1.07	8" HDPE Storm Drain Pipe	53	LF		
BA1.08	Trench Drain	96	LF		
BA1.09	Storm Drain Cleanout	1	EA		
BA1.10	PCC Walkway/Ramp Pavement (Including AB)	3,268	SF		
BA1.11	Stamped Concrete Pattern	930	SF		
BA1.12	Aggregate Base (Under HMA)	168	CY		
BA1.13	Hot Mix Asphalt (Type A)	1	TON		
BA1.14	6' Chain Link Fence	164	LF		
BA1.15	6' Wide Chain Link Gate	2	EA		
BA1.16	18" Wide Concrete Header	159	LF		
BA1.17	Asphalt Concrete Pavement for Pickleball Court	114	TON		
BA1.18	Color Surfacing System	5,949	SF		
BA1.19	10' High Chain Link Fence	256	LF		
BA1.20	3' Wide Chain Link Gate	2	EA		
BA1.21	Wind Screening Material for Pickleball Court	2,300	SF		
BA1.22	Net System and Posts	3	EA		
BA1.23	Bench	3	EA		

BA1.24	Bench Half Round	4	EA		
BA1.25	Picnic Table, ADA Compliant	1	EA		
BA1.26	Trash and Recycling Receptacle (single)	2	EA		
BA1.27	Shade Sail/Awning	1	LS		
Total Bid Alternate 1 Price: (Bid Items BA1.01 through BA1.27)					

Bid Alternate 2 – Concrete Pickleball Courts

ITEM	DESCRIPTION	Quantity	Unit	Unit Price	Item Total
Bid Alternate 2 - Concrete Pickleball Courts					
BA2.01	Mobilization	1	LS		
BA2.02	Construction Staking	1	LS		
BA2.03	Clearing and Grubbing	0.17	AC		
BA2.04	Cut and Fill	378	CY		
BA2.04A	Off-haul Soil Suitable for General Landfill	293	CY		
BA2.05	Fine Grading (Landscape areas only)	962	SF		
BA2.06	8" HDPE Storm Drain Pipe	54	LF		
BA2.07	Storm Drain Inlet	1	EA		
BA2.08	Aggregate Base (Under HMA)	8	CY		
BA2.09	Hot Mix Asphalt (Type A)	5	TON		
BA2.10	6' Chain Link Fence	16	LF		
BA2.11	18" Wide Concrete Header	260	LF		
BA2.12	Post-Tensioned PCC Pavement (Including AB)	4,032	SF		
BA2.13	PCC Walkway/Ramp Pavement (Including AB)	1,579	SF		
BA2.14	Color Surfacing System	5,187	SF		
BA2.15	10' High Chain Link Fence	260	LF		
BA2.16	3' Wide Chain Link Gate	2	EA		
BA2.17	Wind Screening Material for Pickleball Court	2,034	SF		

BA2.18	Net System and Posts	2	EA		
BA2.19	Bleacher	1	EA		
BA2.20	Irrigation Drip System	962	SF		
BA2.21	Compost Soil Amendment	6	CY		
BA2.22	Mulch (3" Thick)	9	CY		
BA2.23	Sheet Mulch Cardboard (2 Layers, Recycled)	962	SF		
BA2.24	Shrubs (1 Gallon)	34	EA		
BA2.25	Shrubs (5 Gallon)	37	EA		
BA2.26	Trees (24" Box)	10	EA		
BA2.27	Decomposed Granite Paving	92	SF		
BA2.28	Bench	2	EA		
BA2.29	Trash and Recycling Receptacle (single)	2	EA		
BA2.30	Landscape Establishment (180 days)	962	SF		
Total Bid Alternate 2 Price: (Bid Items BA2.01 through BA2.30)					

5. Subcontractors for work included in all Bid items are listed on Document 00 4330 (Subcontractors List) submitted herewith.
6. The undersigned Bidder understands that City reserves the right to reject this Bid, but that this Bid shall remain open and shall not be withdrawn for a period of sixty (60) calendar days from the date prescribed for its opening.
7. If written notice of the acceptance of this Bid, hereinafter referred to as Notice of Intent to Award, is mailed or delivered to the undersigned Bidder within the time described in Paragraph 2 of this Document 00 4113 or at any other time thereafter before it is withdrawn, the undersigned Bidder will execute and deliver the documents required by Document 00 2113 (Instructions to Bidders) within the times specified therein.
8. Notice of Award or request for additional information may be addressed to the undersigned Bidder at the address set forth below.
9. The undersigned Bidder herewith encloses cash, a cashier's check, or certified check of or on a responsible bank in the United States, or a corporate surety bond furnished by a surety authorized to do a surety business in the State of California, in form specified in Document 00 2113 (Instructions to Bidders), in the amount of ten percent (10%) of the Total Bid Price and made payable to City of Berkeley.
10. The undersigned Bidder agrees to commence Work under the Contract Documents on the date established in Document 00 7200 (General Conditions) and to complete all Work within the time specified in Document 00 5200 (Agreement).

Tom Bates Regional Sports Complex
Community Facility, Pickleball Courts and U8 Soccer Field

Specification No. 25-11736-C

11. The undersigned Bidder agrees that, in accordance with Document 00 7200 (General Conditions), liquidated damages for failure to complete all Work in the Contract within the time specified in Document 00 5200 (Agreement) shall be as set forth in Document 00 5200.

12. The names of all persons interested in the foregoing Bid as principals are:

IMPORTANT NOTICE: If Bidder or other interested person is a corporation, give the legal name of corporation, state where incorporated, and names of president and secretary thereof; if a partnership, give name of the firm and names of all individual co-partners composing the firm; if Bidder or other interested person is an individual, give first and last names in full.

NAME OF BIDDER: _____

licensed in accordance with an act for the registration of Contractors, and with license number: _____ Expiration: _____.

(Place of Incorporation, if Applicable) (Principal)

(Principal)

(Principal)

I certify (or declare) under penalty of perjury under the laws of the State of California that the foregoing is true and correct.

(Signature of Bidder)

NOTE: If Bidder is a corporation, set forth the legal name of the corporation together with the signature of the officer or officers authorized to sign contracts on behalf of the corporation. If Bidder is a partnership, set forth the name of the firm together with the signature of the partner or partners authorized to sign contracts on behalf of the partnership.

Business Address: _____

Contractor's Representative(s): _____
(Name/Title)

(Name/Title)

(Name/Title)

Tom Bates Regional Sports Complex
Community Facility, Pickleball Courts and U8 Soccer Field

Specification No. 25-11736-C

Officers Authorized to Sign Contracts

(Name/Title)

(Name/Title)

(Name/Title)

Telephone Number(s):

(Area Code)

(Number)

(Area Code)

(Number)

Fax Number(s):

(Area Code)

(Number)

(Area Code)

(Number)

Date of Bid:

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

Tom Bates RSC Community Facility, Pickleball Courts and U8 Soccer Field
Specification No. 25-11736-C

1. Restore appearance, quality, and condition of finished surfacing to match adjacent work, and eliminate evidence of restoration to greatest extent possible.

3.18 DISPOSAL OF SURPLUS AND WASTE MATERIALS

- A. Remove surplus satisfactory soil and waste materials, including unsatisfactory soil, trash, and debris, and legally dispose of them off Owner's property.

PART 4 - MEASUREMENT AND PAYMENT

- A. The Contract unit price paid per CUBIC YARD for CUT AND FILL shall include full compensation for furnishing all labor, material, tools, equipment and incidentals, and for doing all Work involved with excavating and stockpiling earth, filling earth, moisture conditioning, placement in lifts and compaction, as shown on the Plans, as specified in these Technical Specifications and as directed by the Engineer.
- B. The Contract unit price paid per SQUARE FOOT for FINE GRADING shall include full compensation for furnishing all labor, material, tools, equipment and incidentals, and for doing all Work involved with precise leveling and smoothing of the subgrade surface, as specified in these Technical Specifications and as directed by the Engineer.
- C. The Contract unit price paid per CUBIC YARD for DISPOSE CONTAMINATED SOIL shall include full compensation for furnishing all labor, material, tools, equipment and incidentals, and for doing all Work involved with disposing contaminated soil, including testing and hauling, as shown on the Plans, as specified in these Technical Specifications and as directed by the Engineer.
- D. The Contract unit price paid per CUBIC YARD for AGGREGATE BASE shall include full compensation for furnishing all labor, material, tools, equipment and incidentals, and for doing all Work involved with placing and compacting Class 2 aggregate base under asphalt pavement, including the bioswale access road, as shown on the Plans, as specified in these Technical Specifications and as directed by the Engineer.
- E. The Contract unit price paid per CUBIC YARD for PERMEABLE MATERIAL shall include full compensation for furnishing all labor, material, tools, equipment and incidentals, and for doing all Work involved with placing and compacting permeable material in the biofiltration basins, as shown on the Plans, as specified in these Technical Specifications and as directed by the Engineer.
- F. The Contract unit price paid per CUBIC YARD for OFF-HAUL SOIL SUITABLE FOR GENERAL LANDFILL shall include full compensation for furnishing all labor, material, tools, equipment and incidentals, and for doing all Work involved with disposing soil suitable for general landfill, including testing and hauling, as shown on the Plans, as specified in these Technical Specifications and as directed by the Engineer.

END OF SECTION 31 20 00